

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

RECEIVED -3
STATE CORPORATION COMMISSION
APR 14 1982
4-14-82
CONSERVATION DIVISION
Wichita, Kansas
15-141-20,130 V00-00

200 Colorado Derby Building
Wichita, KS 67202

API Number 15-141-20,130 V00-00

Operator's Full Name Rains & Williamson Oil Company, Inc.
Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202
Lease Name Smith Well No. 1
Location SW NE SE Sec. 19 Twp. 10 Rge. 14 (~~East~~) (West)
County Osborne Total Depth 3560'
Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated _____
Plugging Contractor Co. Tools and Halliburton Co.
Address _____ License No. _____
Operation Completed: Hour: 7:45 PM Day: 7 Month: April Year: 1982
Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Anhydrite Top 1010' Elev 1815 KB
Hole circulated and filled with mud. 50 sacks cement pumped through drill pipe at 930'. 30 sacks cement pumped through drill pipe at 240'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Pothole cemented with 10 sacks cement through pipe.

Cement used 50/50 Pozmix w/2% gel and 3% c.c.

Amount of Surface Casing: 8 5/8" (250-135) sacks 50/50 Pozmix w/2% gel 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

At Lindsborg waiting for Service unit to come in on Francis Melland well 1/2 North of Lindsborg

Signed: [Signature]
Conservation Division Agent

INVOICED
DATE 4-16-82
INV. NO. 9951-W

