

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-141-20, 138-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Lawbancos Drilling, Inc.

Complete Address P.O. Box 289, Natoma, Kansas 67651

Lease Name Beisner Well No. 1

Location SW SW NE Sec. 6 Twp. 10 Rge. 19 (~~East~~)(West)

County Osborne Total Depth 3775'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address _____ License No. _____

Operation Completed: Hour: 6:45 PM Day: 15 Month: June Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: Elev. 1954 GL Anhydrite 1188'-1219'.

Hole circulated and filled with mud, 50 sacks cement pumped through drill pipe at 900'; 40 sacks cement pumped through drill pipe at 200'; Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement, Patch cemented with 10 sacks cement.

Cement used: 50/50 lb mix w/2% gel and 3% c.c.

Amount of Surface Casing: 8 5/8" - 165' - 120 sacks

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

On vacation

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1982
6-21-82

CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 6-28-82

INV. NO. 507-W