

15-141-00047-00-00

R  
/

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE-NE-SW

SEC. 14 TWP. 10 RGE. 15W

Dry Hole \*\*\* Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Isenberg.

Operator Jones, Shelburne & Farmer, Address 370 W. Wichita Ave., Russell, Kansas.

Field \_\_\_\_\_ County Osborne.

Total Depth 3655' Feet.

Plugging Contractor Jones, Shelburne & Farmer, Inc.

Plugging Contractor's License No. 263

Address Russell, Kansas.

(Describe Briefly the manner in which the well was plugged)

Surface pipe - 8 5/8" @ 294' c.w.c. 150 sx.

Jet pits up and circulated heavy mud, then pulled pipe out. Run

measuring line with float and found mud at 220' from top. 1/2 sx. hulls,

plug, rock bridge and 20 sx. cem. through drill pipe.

Mud to 40' from top, 1/2 sx. hulls, plug and 10 sx. cem. to base of cellar.

Rock bridge for fresh water plug was tested by supporting the weight

of the drill pipe, plus the weight of the traveling blocks.

Milton Sabard  
District Conservation Agent

Date 9-13-57

9-16-57

PLUGGING  
FILE SEC. 14 T. 10 R. 15W  
BOOK PAGE 45 LINE 32