

15-141-20123-00-00

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 12-22-81
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-141-20, 123-0001

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Northern Lights Oil Company

Complete Address 212 N. Market, Suite 200, Wichita, Kansas 67202

Lease Name Thompson Well No. 1

Location C 5W SW NW Sec. 7 Twp. 10 Rge. 15 (~~East~~) (West)

County Osborne Total Depth 3451'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. and Sun Oilwell Cementing, Inc

Address 617 Union Center, Wichita, Kansas License No. _____

Operation Completed: Hour: 4:30 PM Day: 15 Month: December Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: 8 3/8" - 259' - 175 sacks Fin. 1106' - 42'

Hole circulated and Filled with mud. Pumped 50 sacks
Cement through drill pipe at 900'. 50 sacks cement pumped
through drill pipe at 300'. Hole Filled with mud to 40'. Plug
and 1/2 sack balls pushed to 40' and hole cemented to
base of cellar with 10 sacks cement. Rathole cemented
with 10 sacks cement.

Cement used 50-50 Permox 2% gel 3% cc.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

1-2082
WV. NO. 3994-W