

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: Castelli Exploration, Inc.  
 Address: 6908 NW 112th St., Oklahoma City, OK 73162  
 Phone: (405) 722-5511 Operator License #: 31021  
 Type of Well: Gas Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: \_\_\_\_\_ (Date)  
 by: Steve Durrant (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-033-21249-0000  
 Lease Name: Merrill Ranch  
 Well Number: 2-21  
 Spot Location (QQQQ): 72 - NW - SE - SE  
990 Feet from  North /  South Section Line  
710 Feet from  East /  West Section Line  
 Sec. 21 Twp. 33 S. R. 16  East  West  
 County: Comanche  
 Date Well Completed: 8-8-01  
 Plugging Commenced: 10-23-06  
 Plugging Completed: 10-24-06

*KCC  
PKT  
11-16-06  
per  
CP2/3*

*KCC PKT  
Per CP2/3*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1249	
				4 1/2	4960	4250

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 4895', bailed 4 sacks cement with bailer, ripped casing at 4400', worked pipe, ripped casing at 4250', worked pipe free, pulled casing up to 1300', pumped 15 gel, 50 sacks cement, pulled to 600', pumped 50 sacks, pulled to 40', pumped 10 sacks to surface, pulled joint, tore down floor and rig, backfilled cellar.

Name of Plugging Contractor: Quality Well Service License #: 31925  
 Address: 401 W Main, Lyons, KS 67554

**RECEIVED  
NOV 13 2006**

Name of Party Responsible for Plugging Fees: Castelli Exploration, Inc.  
 State of Oklahoma County, Canadian, ss.

**KCC WICHITA**

Thomas P. Castelli (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Thomas P. Castelli

(Address) 6908 N.W. 112th St. Oklahoma City OK

SUBSCRIBED and SWORN TO before me this 7<sup>th</sup> day of November, 2006



**TISHA L. BRAUN**  
 Canadian County  
 Notary Public in and for  
 State of Oklahoma

Tisha L. Braun  
 Notary Public

My Commission Expires: 6/23/08

*PKT*

# ALLIED CEMENTING CO., INC. 24886

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:  
MEDICINE LODGE

DATE <u>10-24-06</u>	SEC. <u>21</u>	TWP. <u>33s</u>	RANGE <u>16 W</u>	CALLED OUT <u>9:30 am</u>	ON LOCATION <u>12:30 pm</u>	JOB START <u>1:00 pm</u>	JOB FINISH <u>2:15 pm</u>
MEXILL RANCH LEASE		WELL # <u>2-21</u>	LOCATION <u>160+ CO 10 23, 4 S, 9 1/2 E-S-E</u>			COUNTY <u>COMANCHE</u>	STATE <u>KS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)			N/INTO				

CONTRACTOR QUALITY W.S.  
 TYPE OF JOB O.H.P.  
 HOLE SIZE 7 7/8" T.D. 1,300'  
 CASING SIZE 4 1/2" DEPTH 1,300'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 200 MINIMUM 50  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT FRESH WATER

EQUIPMENT

PUMP TRUCK CEMENTER BILL M.  
 # 360 HELPER DWAYNE W.  
 BULK TRUCK  
 # 389 DRIVER JERRY E.  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER CASTELLI EXPLORATION, INC.  
 CEMENT  
 AMOUNT ORDERED 110 SX 60' 40% GEL, 15 SX GEL

COMMON	<u>66</u>	<u>A</u>	@	<u>10.65</u>	<u>702.90</u>
POZMIX	<u>44</u>		@	<u>5.80</u>	<u>255.20</u>
GEL	<u>21</u>		@	<u>16.65</u>	<u>349.65</u>
CHLORIDE			@		
ASC			@		
			@		
			@		
			@		
			@		
			@		
			@		
			@		
			@		
HANDLING	<u>131</u>		@	<u>1.90</u>	<u>248.90</u>
MILEAGE	<u>45</u>	<u>X 131</u>	<u>X</u>	<u>0.09</u>	<u>530.55</u>
TOTAL					<u>2087.20</u>

**RECEIVED**  
**NOV 13 2006**  
**KCC WICHITA**

**REMARKS:**

1st plug, 1300', load hole with 15sx GEL, pump 50 sx 60:40% GEL, displace with fresh water, 2nd plug, 600', load hole, pump 30 sx 60:40% GEL, displace with fresh water, 3rd plug, 40', load hole, pump 10 sx 60:40% GEL, circulate cement to surface,

CHARGE TO: CASTELLI EXPLORATION, INC.  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Richard M. McIntyre

SERVICE

DEPTH OF JOB	<u>1,300'</u>				
PUMP TRUCK CHARGE				<u>720.00</u>	
EXTRA FOOTAGE		@			
MILEAGE	<u>45</u>	@	<u>6.00</u>	<u>270.00</u>	
MANIFOLD		@			
		@			
		@			
TOTAL					<u>990.00</u>

PLUG & FLOAT EQUIPMENT

	@			
	@			
	@			
	@			
ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING				
TOTAL				_____

TAX \_\_\_\_\_  
 TOTAL CHARGE ~~3874.10~~  
 DISCOUNT ~~1000.00~~ IF PAID IN 30 DAYS

RICHARD MCINTYRE  
 PRINTED NAME