

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Southern Star Central Gas Pipeline
 Address: 4700 Highway 56 P.O. Box 20010 Owensboro, Kentucky
 Phone: (270) 852-4490 Operator License #: 33097
 Type of Well: Gas Storage Observation Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 7/25/2006 (Date)
 by: Doug Louis (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Kansas City Ls. Obs. Well Depth to Top: 2439' Bottom: 2661' T.D. 3333'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-19171-00-02
 Lease Name: Alden Gas Storage
 Well Number: 0-13
 Spot Location (QQQQ): AW-SW-SW-SW
395 Feet from North / South Section Line
5093 Feet from East / West Section Line
 Sec. 22 Twp. 5104 S. R. 9 East West
 County: Rice
 Date Well Completed: 11-20-1937
 Plugging Commenced: 9/5/2006
 Plugging Completed: 9/6/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City Ls.	saltwater	0	3333'	7"		1900'
	surf		49'	16"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plug back from 3333'-2930' on 10-6-1960 with 445 sks. On 9-5-2006 ran 2 3/8" tubing to 2700' and pumped 75 sks., spotted drilling mud, and pumped another 75 sks.

On 9-6-2006, shot 7" casing at 1900' and pulled casing out of hole. Ran back in hole with 2 3/8" tubing to 1900' and pumped 50 sks., pumped 75 sks. at 1200', pumped 75 sks. at 750', pumped 200 sks. from 500' to surface. The well was capped and buried 5" below surface.

Site reclaimed.

Name of Plugging Contractor: Gressel Oilfield Service Inc. Kings Well Serv Inc License #: 3004 33728
 Address: P.O. Box 607 Burrton, Kansas 67020

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

State of Kentucky County, Daviess, ss.

D. Mark Rouse Staff Geologist

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) D. Mark Rouse SSCGP

(Address) 4700 Hwy. 56 Owensboro, Ky. 42304

SUBSCRIBED and SWORN TO before me this 30th day of October, 2006

Shelley R Rouse My Commission Expires: 10-30-2009
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC PPT
01 PercP2/3
11-16-06

KCC
PPT
Per
Figs
CPSD

KCC
11-16-06
PPT
per
RBDMS

KCC PPT
11-16-06
per RBDMS
C P 2/3

RECEIVED
NOV 03 2006
KCC WICHITA