


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Lincoln County. Sec. 14 Twp. 10S Rge. 9 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines C NE SE  
Lease Owner Irving Nagel & National Drilling Co., Inc.  
Lease Name Peckham Well No. 1  
Office Address 535 Petroleum Building, Wichita, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed January 21, 1961  
Application for plugging filed January 21, 1961  
Application for plugging approved January 21, 1961  
Plugging commenced January 21, 1961  
Plugging completed January 21, 1961  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, Victoria, Kansas.  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4306 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with Drilling Mud to 200'. Set plug and cemented with 20 sacks thru drill pipe. Mudded hole to 40' cemented with 20 sacks.

01-27-1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor National Drilling Company, Inc.  
Address 535 Petroleum Building, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss. \_\_\_\_\_ contractor  
Howard A. Stoskopf, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 25th day of January, 1961

Hershel Hays  
Notary Public.

My commission expires 12-3-64




KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **IRVING NAGEL & NATIONAL DRILLING CO. INC** SEC. 14 T. 10S R. 9W  
**15-105-00013-00-00** LOC. C NE SE  
FARM **Peckham** NO. 1

TOTAL DEPTH **4306'**  
COMM. **1-10-61** COMP. **1-21-61**  
SHOT OR TREATED  
CONTRACTOR **National Drilling Co., Inc.**  
ISSUED

COUNTY **Lincoln**  
KANSAS



CASING  
20 10  
15 8  $\frac{3}{8}$ " 205' cem. w/150 sacks cement  
12 6  
13 5

ELEVATION **1562' RB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

			<u>TOPS</u>
Clay & post rock	50		
clay shale & w/sand strks	205		
shale	330	Topeka	2370 - 808
sand	395	Heebner	2606 - 1041
shale & red bed	650	Lansing	2708 - 1146
shale & shells	1240	B/X.C.	3036 - 1474
lime & shale	1745	Mississippi	3308 - 1746
shale & shells	2320	Hunton	3514 - 1952
lime & shale	2960	Viola	3650 - 2088
lime	3075	Simpson	3852 - 2290
lime & shale	3305	Arbuckle	3914 - 2352
Mississippian	3405	Reagen	4284 - 2724
lime & shale	3547		
shale, chalk & lime	3564	RTD	4306
lime & shale	3915		
lime	3995		
Arbuckle	4008		
lime	4284		
Sand Reagen	4290		
Reagen	4300		
sand	4306		
Rotary Total Depth	4306		

KANSAS GEOLOGICAL SOCIETY  
WELL LOG COMMISSION  
JAN 27 1961  
01-27-1961  
GEOLOGICAL SURVEY  
WICHITA, KANSAS

I hereby certify that the above is a true and correct log of the above described well as shown by the drilling reports.

NATIONAL DRILLING COMPANY, INC.

*Howard A. Stoskopf*  
Howard A. Stoskopf, President

STATE OF KANSAS )  
                          ) SS:  
SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 25th day of January, 1961.

My Commission Expires  
December 3, 1964

*Geraldine Hays*  
Geraldine Hays, Notary Public