


15-105-00009-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 N. Broadway  
Wichita, Kansas

Lincoln County. Sec. 1 Twp. 10 Rge. (E) 7 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE NE  
Lease Owner Donald T. Ingling et al  
Lease Name Brockway Well No. 1  
Office Address Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 29, 1957  
Application for plugging filed August 29, 1957  
Application for plugging approved August 29, 1957  
Plugging commenced August 29, 1957  
Plugging completed August 29, 1957  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Milton Galyardt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3885' Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	351'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Layed down drill pipe to plug well. Put solid bridge at 320 feet, mixed 20 sacks cement on bottom plug, filled hole to within 40 feet of top and put 10 sacks cement on top of plug. Mr. Galyardt was present to supervise the plugging.



(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Donald T. Ingling  
Address 623 1st Nat'l Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. D. T. Ingling (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. T. Ingling  
623 1st Nat'l Bank Bldg., Wichita 2  
(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of September, 19 57

My commission expires Feb. 27, 1960

W. E. Black  
Notary Public.

PLUGGING  
FILE SEC 1 T. 10 R. 7W  
BOOK PAGE 41 LINE 37

WELL LOG - BROCKWAY NO. 1

15-105-00009-00-00

Donald T. Ingling, et al, Lease Owner

Section 1-10-7W

Donald T. Ingling, Contractor

Location: NE NE NE

Commenced: 8-12-57

County: Lincoln

Completed: 8-29-57

Production: Dry

Total Depth: 3885'

Elevation: 1376 DF

Casing: 8 5/8" 351' (175 sacks cement)

Figures below indicate bottom formation

40	surface clay	3065	shale
230	shale	3130	shale
352	shale and shells	3144	shale
390	shale and shells	3185	Mississippi
540	shale and shells	3225	cherty
600	lime	3263	lime
790	shale and shells	3310	lime
1030	shale and lime	3339	lime
1200	lime	3385	lime and sandy shale
1385	lime	3418	shale
1523	lime and sand streaks	3441	lime - Hunton
1615	lime and shale	3490	lime
1680	shale	3515	lime
1840	shale	3540	shale
1900	lime and shale	3582	shale
2030	shale and lime streaks	3605	lime - Viola
2120	lime	3643	lime
2217	lime	3680	lime
2330	lime	3720	lime
2348	lime	3750	lime
2423	shale and sand	3780	lime
2450	lime and shale	3815	lime
2470	lime and shale	3865	lime and shale
2506	lime	3885	Arbuckle
2600	lime	3885	Total Depth
2665	lime		
2722	lime		
2780	lime		
2855	lime		
2910	lime		
2963	lime		

STATE OF KANSAS  
 SEP 7 1957  
 COUNTY CLERK  
 WICHITA, KANSAS

I certify this is a true and correct copy of the above mentioned well.

STATE OF KANSAS )  
                          ) SS.  
SEDGWICK COUNTY )

D. T. Ingling

Subscribed and sworn to before me, a Notary Public, in said county and state.

M. E. Black  
Notary Public

My commission expires: 2-27-60

PLUGGING  
 FILE SEC 1 T 10 R 7W  
 BOOK PAGE 41 LINE 37