

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: J MARK RICHARDSON FAMILY TRUST/dba RICHARDSON OIL
Address: 1406 N CHARLES
Phone: (316) 263-0080 Operator License #: 33388

Type of Well: OIL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7/20/06 (Date)
by: DAVID WILLIAMS (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)
CHEROKEE Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-097215530000
Lease Name: PARKIN
Well Number: 2
Spot Location (QQQQ): SW - SW - NE - NW 11/20/06
2310 2943 Feet from North / South Section Line KCC
2310 2299 Feet from East / West Section Line PRT per OPS. Pigs
Sec. 2 Twp. 30S S. R. 19W East West
County: KIOWA
Date Well Completed: 1/25/2005
Plugging Commenced: 6/20/06
Plugging Completed: 08/08/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	681	0
				4 1/2	5097	<u>1248 2038'</u> <u>KCC PRT per CP2/3</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

SEE ATTACHED

Name of Plugging Contractor: PLAINS, LLC License #: 33645

Address: P O BOX 346 NESS CITY, KS 67560

Name of Party Responsible for Plugging Fees: RICHARDSON OIL

State of KANSAS County, SEDGWICK, ss.

KIM SANTELLAN (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kim Santellan
(Address) 1406 N CHARLES WICHITA KS 67203

RECEIVED
NOV 17 2006

SUBSCRIBED and SWORN TO before me this 16TH day of NOVEMBER

Brenda Hartley My Commission Expires: _____
Notary Public

KCC WICHITA 20 06
BRENDA HARTLEY
Notary Public - State of Kansas
My Appt. Expires 1-8-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PRT



Schmidt Engineering, Inc.

1321 West 93rd North • Valley Center, Kansas • 67147 • (316) 755-3523

RICHARDSON OIL OPERATING

Parkin #2
Kiowa County, KS

Well Plugging Report

08/07/06: RU Plains LLC. Clark Corp. dug out braden head & circulating pit and leveled location. RU Log Tech. Set 4 1/2" CIBP @ 3470' w/ 4 sx cement. Weight indicator on rig does not read properly. Attempt pipe cut @ 3007', 2563', 2208'. No success. Shut down for night. Wait on functional weight indicator.

08/08/06: Plains LLC replaced weight indicator. Rig up Log Tech. Locate and cut 4 1/2" casing @ 2038'. Pull out w/ 18 jts to 1246'. Will pump cement plug in AM and lay down remainder casing.

08/09/06: Rig up Allied Cementing. Mix 15 sxs gel w/ 300# hulls & pump @ 1246' + 50 sxs 60/40 poz w/ 6% gel. Pull casing to 718' mix & displace 50 sxs 60/40 poz 6% gel. Pull casing to 366' - mix & displace 40 sxs 60/40 poz 6% gel. Pull csg to 44' - mix & displace 25 sxs 60/40 poz 6% gel to surface, lay down 46 jts 4 1/2" 10.5# csg total. Plugging operation witnessed by Eric w/ KCC. Rig down Allied. Remove 8 5/8" casing head & rig down Plains LLC. Will have cellar & pit backfilled.

Charles Schmidt
Petroleum Engineer

Allan Walker
Field Supervisor

RECEIVED

NOV 17 2006

KCC WICHITA

Plains, LLC
P.O. Box 346
Ness City, KS 67560

Invoice

Phone #	Fax #
785-798-3995	785-798-2592

Date	Invoice #
8/18/2006	1600
WORK TICKET #'S	
19735 - 18955	

Bill To
Richardson Oil 1406 N Charles Wichita, KS 67203

POSTED
 BY _____ DATE _____

LEASE
 Parkins #2

Description	RIG #	LEASE	
	16	Parkins #2	
	Hours	Rate	Amount
8-7 Drove to the location, rigged up, rigged up Log-Tech, tried 3 different times to cut off the casing, shut down for the night.			
Rig #16	8	181.00	1,448.00T
12% Fuel Surcharge	1,448	0.12	173.76T
Solvent	5	4.00	20.00T
4 1/2" Elevators	1	150.00	150.00T
8-8 Drove to the location, rigged up Log-Tech to cut off casing, rigged down Log-Tech, pulled out 18 joints of casing, shut down for the night.			
Rig #16	4	181.00	724.00T
12% Fuel Surcharge	724	0.12	86.88T
Tubing Tongs	1	125.00	125.00T
Solvent	5	4.00	20.00T
8-9 Drove to the location, rigged up Allied, pumped cement down the well, laid down 12 joints, pumped cement on the second plug, pulled out 8 joints, pumped cement on the third plug, pulled out 7 joints and cemented all the way to surface, rigged down, cleaned up the location, moved off.			
Rig #16	3	181.00	543.00T
12% Fuel Surcharge	543	0.12	65.16T
Tubing Tongs	1	125.00	125.00T
Solvent	5	4.00	20.00T
KIOCO Sales Tax		6.30%	220.55
Total			\$3,721.35

RECEIVED
 NOV 17 2006
 KCC WICHITA