

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Shakespeare Oil Company, Inc.
Address: 202 West Main Street, Salem, IL 62881
Phone: (618) 548 - 1585 Operator License #: 7311
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/25/06 (Date)
by: Herb Dinas (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 063-20856 -06-01
Lease Name: Selensky
Well Number: 1-15
Spot Location (NOOQ): SE - NW - SE - NE
1815 feet from North / South Section Line
900 feet from East / West Section Line
Sec. 15 Twp. 12 S. R. 28 East West
County: Gove
Date Well Completed: 7/26/06
Plugging Commenced: 7/26/06
Plugging Completed: 7/26/06

KCC 11/22/06
PRT per
Figs G.P.S.O.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0'	1230'	8 5/8"	1230'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Cement plugs from 2140' to 2015', 1295' to 795', 191' to surface and topped off csg.

Rotary mud from 2015' to 1295', 795' to 191'

A total of 160 sx 60/40 Pozmix, 6% gel & 1/4# Floseal was placed by drillpipe and cemented by Allied Cementing Co., Inc.

Name of Plugging Contractor: Wild West Well Service License #: 32592
Address: PO Box 433, Ness City, KS

Name of Party Responsible for Plugging Fees: Shakespeare Oil Company, Inc.
State of Illinois County, Marion, ss.

Donald R. Williams, Vice President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Donald R. Williams
(Address) 202 West Main St., Salem, IL 62881

SUBSCRIBED and SWORN TO before me this 14th day of November, 2006
Melissa A. McCormick My Commission Expires: 4-11-07
Notary Public

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NOV 16 2006

KCC WICHITA

PRT