


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

OSBORNE County, Sec. 15 Twp. 10 Rge. 11 (E) (W) x



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner DROLTE & CHRISTOPHER ET AL
Lease Name NICHOLS Well No. 1
Office Address 624 PETROLEUM BUILDING, AMARILLO, TEXAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed DECEMBER 23 19 50
Application for plugging filed DECEMBER 23 19 50
Application for plugging approved DECEMBER 23 19 50
Plugging commenced DECEMBER 23 19 50
Plugging completed DECEMBER 23 19 50
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES - LOU BROCK - GREAT BEND, KANSAS

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4144 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 183' | NONE |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

CEMENTED BOTTOM PLUG @ 160' WITH 20 SACKS
TOP PLUG AT 35' WITH 10 SACKS



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor HILTON DRILLING COMPANY, INC.
Address 925 PATTON, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
HENRY PEACOCK - LAND DEPARTMENT (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Henry Peacock
HENRY PEACOCK
GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 29TH day of DECEMBER, 1958
Carman Reinhardt Leiker
Notary Public.

My commission expires JANUARY 26, 1959

PLUGGING
FILE SEC. 15 T. 10 R. 11W
BOOK PAGE 7 LINE 25

DRILLER'S LOG

15-141-00004-00-00

| | | | |
|-------------|-------------------------------|--------------|--|
| COMPANY: | DROLTE & CHRISTOPHER ET AL | LOCATION: | NW NW NW SECTION 15-10-11 OSBORNE COUNTY, KANSAS |
| CONTRACTOR: | HILTON DRILLING COMPANY, INC. | ELEVATION: | 1730 DF |
| FARM NAME: | NICHOLS # 1 | CASING USED: | 8-5/8" @ 183' WITH 175 SACKS |
| COMMENCED: | DECEMBER 10, 1958 | | |
| COMPLETED: | DECEMBER 23, 1958 | | |

| | |
|-------------------|------|
| SOIL AND CLAY | 50 |
| SAND | 70 |
| SHALE AND SHELLS | 182 |
| SHALE | 425 |
| SHALE AND SAND | 500 |
| RED BED | 525 |
| RED BED AND SHALE | 740 |
| ANHYDRITE | 770 |
| SHALE AND SHELLS | 1420 |
| LIME AND SHALE | 1820 |
| LIME | 1895 |
| LIME AND SHALE | 3100 |
| LIME | 3580 |
| CHERT | 3610 |
| LIME AND CHERT | 3672 |
| LIME | 3760 |
| LIME AND SHALE | 3840 |
| LIME | 4020 |
| LIME AND SHALE | 4144 |
| TOTAL DEPTH | 4144 |

STATE OF KANSAS)
 SS
COUNTY OF BARTON)

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE DESCRIBED.

HILTON DRILLING COMPANY, INC.

Henry Peacock
HENRY PEACOCK - LAND DEPARTMENT

SUBSCRIBED AND SWORN TO BEFORE ME THIS 29TH DAY OF DECEMBER, 1958:

Carmen Reinhardt Leiker
NOTARY PUBLIC

MY COMMISSION EXPIRES JANUARY 26, 1959.

RECEIVED
STATE CORPORATION COMMISSION
12-30-1958
DEC 30 1958
DIVISION

| | |
|----------|-------------------|
| PLUGGING | |
| FILE | SEC 15 T 10 R 11W |
| BOOK | PAGE 1 LINE 25 |