


15-141-00024-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biffing Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Osborne County. Sec. 26 Twp. 10 Rge. 15 (E) W (W)  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NE NE  
Lease Owner Duke & Wood Drilling Company, Inc.  
Lease Name Koelling Well No. 1  
Office Address Box 194, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 9, 19 52  
Application for plugging filed March 9, 19 52  
Application for plugging approved March 9, 19 52  
Plugging commenced March 9, 19 52  
Plugging completed March 9, 19 52  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 3433 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	205'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud, set bottom plug at 210 ft., dumped 15 sacks of cement on plug thru drill pipe. Filled hole w/mud to 35 ft., set top plug, dumped 10 sacks of cement filled to bottom of cellar.

Received  
4-2-52

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Duke & Wood Drilling Company, Inc.  
Address Box 194, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
Cecil M. Olson (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Cecil M. Olson  
Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 31st day of March, 19 52

Notary Public

My commission expires April 29, 1953.

23-5091-s 8-50-10M

PLUGGING  
FILE SEC 26 T 10 R (SW)  
BOOK PAGE 149 LINE 34

15-141-000 24-00-00

WELL LOG  
Koelling #1  
NW NE NE of Section 26-10-15W  
Osborne County, Kansas

Elevation 1803 D. F.  
Anhydrite 975 (-830)  
Heebner 2944 (-1139)  
Lansing 2989 (-1184)  
Conglomerate 3356 (-1551)

0-70	Surface clay, post rock & shale
70-125	Sand, shale and clay
125-205	Shale
205-430	Shale and clay
430-565	Sand and iron
565-690	Sand, shale and clay
690-975	Sand and red bed
975-1010	Anhydrite
1010-1290	Shale and shells
1290-1400	Salt and shale
1400-1640	Broken Lime
1640-1995	Broken Lime
1995-2325	Shale and lime
2325-2710	Shale and lime
2710-2770	Shale and lime
2770-2860	Lime
2860-2965	Lime
2965-3094	Lime
3094-3190	Lime
3190-3312	Lime
3312-3400	Lime
3400-3433	Cherty conglomerate
3433	TOTAL ROTARY DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton .SS

I, Lynn O. Duke, of the DUKE & WOOD DRILLING COMPANY, INC.  
being first duly sworn on oath, state; That I have knowledge of the facts,  
statements and matters herein contained and that the same are true and correct.

Lynn O. Duke  
Vice - President

Subscribed and sworn to before me this 1st day of April 1952.

PLUGGING  
FILE SEC 26 10 15W  
BOOK PAGE 149 LINE 54

Dean T. Cooley  
Notary Public

My commission expires: April 29, 1953.

Received  
4-2-52