

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-21249-00-00  
Spot: N2SESE Sec/Twnshp/Rge: 21-33S-16W  
990 feet from S Section Line, 710 feet from E Section Line  
Lease Name: MERRILL RANCH Well #: 2-21  
County: COMANCHE Total Vertical Depth: 4985 feet

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 N.W. 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4960	4250	
SURF	8.625	1249		

\$ 162.01

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/24/2006 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICKEY POPP Company: CASTELI EXPLORATION, INC. Phone: (620) 786-5514

Proposed Plugging Method: SANDED TO 4895' WITH 4 SX CMT. PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/24/2006 2:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 4895' WITH 4 SX CMT. 1ST PLUG AT 1300' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. GOOD RETURNS CEMENT CIRCULATED

Perfs:

Top	Bot	Thru	Comments
4960	4985		OH
4945	4947		4 SPF

**INVOICED**  
DATE 11-21-06  
INV. NO. 2007060850

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED CEMENTING CO., INC. RECOVERED 4250' CASING.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
(TECHNICIAN)

RECEIVED Form CP-2/3  
NOV 20 2006  
KCC WICHITA

*[Handwritten Signature]*  
PKT