

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

KEEP PER 11/20/06  
PER OPS FTGS.

API Well Number: 15-051-02875-00-01

Spot: SWNWSW

Sec/Twnshp/Rge: 20-13S-20W

1731 ~~1650~~ feet from S Section Line, 330 feet from W Section Line

Lease Name: FLAX

5062 Well #: 2

County: ELLIS

Total Vertical Depth: 3906 feet

Operator License No.: 32754

Op Name: ELYSIUM ENERGY, L.L.C.

Address: 1625 BROADWAY, STE 2000  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3894	0	w/200 sxs cmt
SURF	8.625	184	0	w/150 sxs cmt \$126.95

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/09/2006 9:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: GARY L.

Company: ELYSIUM ENERGY, LLC

Phone: (785) 625-4052

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Squeeze jobs: 2002 - 1275' - 1307' w/170 sxs.  
2002 - 1815' - 1974' w/250 sxs.  
2001 - 2132' - 2162' w/125 sxs.  
1993 - 2178' - 2437 w/200 sxs.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/09/2006 11:00 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1318'. Allied pumped 100 sxs 60/40 pozmix - 10% gel with 100# hulls - circulated cement out both 8 5/8" and 5 1/2".  
Shut in backside.  
PTOH. Allied pumped 20 sxs down 5 1/2" casing.  
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3300	3906		

INVOICED  
DATE 11-21-06  
INV. NO. 20070608S/

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

*Richard Williams*

(TECHNICIAN)

RECEIVED

NOV 20 2006

KCC WICHITA

Form CP-2/3

NOV 13 2006

PKT

ELYSIUM ENERGY LLC  
DENVER CO 80202

20-13S-20W  
SW NW SW

#2 FLAX A OWWO

site: 1-3/4 S & 1/4 W OF ELLIS KS      city: ELLIS      API 15-051-02875  
contr: CHITO'S WELL SVC      field: HERBERT SD  
prod: NONE  
fr date 01/13/2003      spd date 10/25/2002      orig comp 10/25/2002      card issued 01/13/2003      last revised 01/13/2003


ELV: 2258 KB, 2253 GL LOG
tops.....depth/datum
ANH.....1576 +682
B/ANH.....1622 +636
TOP.....3271 -1013
HEEB.....3503 -1245
TOR.....3523 -1265
LANS.....3540 -1282
MARM.....3832 -1574
LTD OLD.....3888 -1630
ARB.....3892 -1634
RTD OLD.....3893 -1635
DDTD OLD.....3906 -1648

IP status  
OIL, P 8.6 BO & 347 BWPD, SHAW 3300-3304 , LKC  
3582-3726 OA , MARM 3846-3853 , ARB 3894-3906 ,  
11/21/2002  
OLD INFO: OPERATOR WAS BIRMINGHAM-BARTLETT  
DRLG CO, 2 FLAX, SPD 05/19/1961, 05/28/1961 8-5/8" 184, 5-  
1/2" 3894, OIL, P 108 BOPD, NW, ARB 3894-3906 ,  
07/14/1961(CARD ISSUED 07/21/1961)  
CONTR: BIRMINGHAM-BARTLETT  
COMMENT: WAS TEMP ARI IOG-5946  
DRLR SD ZNS: 30-184 (W/SH), 1090-1275

COPYRIGHT 2003  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

(over)

ELYSIUM ENERGY LLC  
DENVER CO 80202

20-13S-20W  
SW NW SW

#2 FLAX A OWWO

NO CORES

DST (1) 3602-3633 (LANS), / 20-15-30-15, REC 5400' TF: 360' OIL, 1800' WTR, REMARK: FP NA ISIP 1100# FSIP 1075#  
DST (2) 3669-3715 (KC), / 20-20-0-0, REC 10' M, NS, REMARK: FP NA ISIP 0#  
DST (3) 3722-3755 (KC), / 30-15-30-15, REC 60' M, NS, REMARK: FP NA ISIP 740# FSIP 60#  
DST (4) 3762-3790 (KC), / 15-15-0-0, REC 5' M, NS, REMARK: FP NA ISIP 0#  
MICT - CO TO 3893, (ARB OH), DD 3906 TD, SWB 2 BOFH, NW/8 HRS, NAT, AC 500 GAL, SWB LD, GSO, POP, IPP 108 BOPD, NW, 7/14/1961  
NEW INFO: FR 01/13/2003, REWORKED 10/25/2002 DC 10/25/2002  
COMMENT: GRN LOG RUN 1/12/2002  
MICT - CO, SQZ'D CSG LEAK FROM 1815-1974, W/250 SX, SQZ'D CSG LEAK FROM 1275-1307 W/170 SX, CO, PF (MARM) 3846-3853, W / 2 SFF, SWB DWN, SO, NAT, AC 250 GAL (15% NE), SWB LD, SO, PF (LKC) 3582-3584, 3699-3704, 3724-3726, W / 2 SFF, AC EA ZN W/250 GAL (15% NE), SWB LD, SO, PF (TOP) 3300-3304, W / 2 SFF, AC 250 GAL (15% NE), SWB LD, SO, SET 2-7/8" TBG AT 3890, NO PKR, POP, IPP 8.6 BO & 347 BWPD, RESUMED PROD 11/21/2002, COMMINGLED W/OLD PAY (ARB 3894-3906)