

KCC PKT
11-16-06 per GPS Figs.

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05804-00-00

Spot: NWNWSW

Sec/Twnshp/Rge: 22-11S-17W

2305 ~~2310~~ feet from S Section Line, 4950 feet from E Section Line
4991

Lease Name: BEMIS

Well #: 1

County: ELLIS

Total Vertical Depth: 3412 feet

Operator License No.: 3273

Op Name: LOEB, HERMAN L.

Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	15	100		
PROD	7	3397	0	w/unknown sxs cmt
SURF	10	1117	0	w/unknown sxs cmt

\$ 110.89

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/01/2006 11:00 AM

Plug Co. License No.: 32028

Plug Co. Name: CHITO'S WELL SERVICE, LLC

Proposal Rcvd. from: ROLAND NYE

Company: LOEB, HERMAN L.

Phone: (785) 425-7387

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 1000# hulls.
08/31/2006 - Dug out - has cement box cellar - found no 15' casing - no records on well.
L.K. Wireline perfed at 675' - 1150' - 1675'.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/01/2006 2:15 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Chito's Well service RIH with tubing to 2056'.
Allied riggd to tubing and pumped 200 sxs 60/40 pozmix with 700# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 55 sxs with 100# hulls mixed in to circulate cement out of backside.
Pulled tubing - topped 4 1/2" casing with 5 sxs cement. Hole standing full.

Top	Bot	Thru	Comments
3397	3412	OH	

INVOICED
DATE 11-17-06
INV. NO. 2007060828

Remarks: ALLIED CEMENTING COMPANY-TICKET #26047.

Plugged through: TBG

District: 04

HD

Signed

(TECHNICIAN)

RECEIVED

NOV 07 2006

Form CP-2/3

KCC WICHITA

NOV 02 2006

PKT

BRITISH AMERICAN OIL PROD #1 BEMIS

22-11-17W
NW NW SW

Contr. _____


ELLIS County

E 1904 Comm 11-21-36 Comp 12-31-36 IP

2168 BOPD

Tops	Depth	Datum
ANH	1114	
TOP	2835	
LANS	3155	
CONG	3362	
SIMP	3397	
ARB	3408	
TD	3412	

Casing
 15" 100
 10" 1117
 7" 3397
 4 1/2" 3497
 Swb 1816 BO/24 hrs
 Pmp 70 BOPH
 @WWO
 DD 3507 4" Liner 3497
 16/3438-43
 Pmp 2280+758w/24



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS