

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC 11-16-06 PKT
per F10
GPSD

API Well Number: 15-063-21453-00-01

Spot: NENENW

Sec/Twnshp/Rge: 15-11S-31W

4821.950 feet from S Section Line, 2970 feet from E Section Line

Lease Name: B WARD

3049

Well #: 1

County: GOVE

Total Vertical Depth: 4690 feet

Operator License No.: 4767

Op Name: RITCHIE EXPLORATION, INC.

Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	4687	0	200 SX CMT
------	-----	------	---	------------

SURF	8.625	209	0	140 SX CMT
------	-------	-----	---	------------

\$ 152.43

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/02/2006 9:00 AM

Plug Co. License No.: 99998

Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: PETER FIORINI

Company: RITCHIE EXPLORATION, INC.

Phone: (785) 623-1506

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 600# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 11/02/2006 11:00 AM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 209' w/140 sxs.
4 1/2" production casing set at 4687' w/200 sxs.
PBSD 4660'. TD 4690'.
Port collar set at 2530' w/425 sxs.
Connected to 4 1/2" production casing - pumped 240 sxs cement with 600# hulls.
Max. P.S.I. 250#. S.I.P. 100#.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.
Max. P.S.I. 150#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
4628	4632		
4260	4264		
4206	4209		
4131	4134		

INVOICED
DATE 11-17-06
INV. NO. 2007060829

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman
(TECHNICIAN)

RECEIVED

Form CP-2/3

NOV 07 2006

KCC WICHITA

NOV 02 2006

PKT

replacement card

RITCHIE EXPLORATION
WICHITA KS 67202

15-11S-31W
NE NE NW

#1 WARD, B.

site: 1-1/4 S & 6 W OF GRINNELL KS ay: GOVE API 15-063-21453
 contr: WHITE & ELLIS #9 field: KEARNS EXT (1/8 W)
 geol: KITT NOAH

fr date 04/08/93 spd date 10/09/93 drig comp 10/20/93 card issued 01/31/94 last revised 04/29/96

ELV: 3004 KB, 2999 GL LOG

tops.....	depth/datum
ANH.....	2529 + 475
B/ANH.....	2556 + 448
HEEB.....	4014 -1010
LANS.....	4057 -1053
MUN CR.....	4188 -1184
STARK.....	4275 -1271
BKC.....	4337 -1333
MARM.....	4366 -1362
PAW.....	4467 -1463
MYR STA.....	4505 -1501
FT SCOTT.....	4532 -1528
CHER.....	4558 -1554
JOHNSON ZN.....	4604 -1600

IP status:
 OIL, P 24 BO & 62 BWP, LKC 4131-4264 OA, 11/19/93
 PBDT.....4612 -1608
 CONG SD.....4628 -1624
 MISS.....4643 -1639
 MISS DOL.....4660 -1656
 RTD.....4660 -1656
 LTD.....4690 -1686
 INFO RELEASED: 4/29/96 - WAS OIL WELL - TIGHT HOLE
 CSG: 8-5/8" 209 / 140 SX (ALT 2), 4-1/2" 4687 / 200 SX,
 MULTI STAGE COLLAR AT 2530 / 650 SX

COPYRIGHT 1996
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

replacement card

RITCHIE EXPLORATION
WICHITA KS 67278

15-11S-31W
NE NE NW

#1 WARD, B. OWWO

site: 1-1/4 S & 6 W OF GRINNELL KS ay: GOVE API 15-063-21453
 contr: UNKNOWN field: KEARNS
 geol: NONE

fr date 04/02/2001 spd date 01/10/2000 drig comp 01/10/2000 card issued 04/02/2001 last revised 08/26/2002

ELV: 3004 KB, 2999 GL LOG

tops.....	depth/datum
ANH.....	2529 +475
B/ANH.....	2556 +448
HEEB.....	4014 -1010
LANS.....	4057 -1053
MUN CR.....	4188 -1184
STARK.....	4275 -1271
BKC.....	4337 -1333
MARM.....	4366 -1362
PAW.....	4467 -1463
MYR STA.....	4505 -1501
FT SCOTT.....	4532 -1528
CHER.....	4558 -1554
JOHNSON ZN.....	4604 -1600

IP status:
 OIL, P 5 BO & 81 BWP, LKC 4131-4264 OA, CONG
 4628-4632 , (NEW PAY) , 01/14/2000
 PBDT.....4612 -1608
 CONG SD.....4628 -1624
 MISS.....4643 -1639
 MISS DOL.....4660 -1656
 RTD OLD.....4690 -1686
 LTD OLD.....4690 -1686
 INFO REL: 8/26/2002 - WAS OIL WELL - TEMP COMP
 NOTE: INFO REL 4/29/1996 - WAS OIL WELL - TIGHT HOLE
 OLD INFO: OPERATOR WAS RITCHIE EXPLORATION, 1
 WARD, B., SPD 10/09/1993, 10/20/1993 8-5/8" 209 / 140 SX
 (ALT 2), 4-1/2" 4687 / 200 SX, MULTI STAGE COLLAR AT
 2530 / 650 SX, OIL, P 24 BO & 62 BWP, LKC 4131-4264 OA,

COPYRIGHT 2002
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)