

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23224-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 25-10S-23W  
2310 feet from N Section Line, 1680 feet from E Section Line  
Lease Name: BOLLIG C Well #: 2-25  
County: GRAHAM Total Vertical Depth: 4055 feet

Operator License No.: 3293  
Op Name: RUSSELL OIL, INC.  
Address: P.O. BOX 1469  
PLAINFIELD, IL 60544

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	219		

\$ 131.79

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2006 12:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: BURT BEERY Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: NONE  
Date/Time Plugging Completed: 11/14/2006 1:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 1900' w/25 sxs.  
2nd. Plug at 1025' w/100 sxs.  
3rd. Plug at 275' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Perfs:

INVOICED

DATE 11-20-06  
INV. NO. 2007060840

Remarks: QUALITY WELL CEMENTING.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

NOV 14 2006

RECEIVED  
NOV 16 2006  
KCC WICHITA

Form CP-2/3

PS