

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-27058-00-00  
Spot: <sup>SW</sup> NENWSE Sec/Twnshp/Rge: 30-23S-17E  
2010 feet from S Section Line, 1825 feet from E Section Line  
Lease Name: BRUNER Well #: 15  
County: WOODSON Total Vertical Depth: 917 feet

Operator License No.: 32903  
Op Name: TRIPLE B CRUDE, LLC  
Address: 2100 WEST VIRGINIA RD  
COLONY, KS 66015

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	

\$ 35.00

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/03/2006 10:00 AM  
Plug Co. License No.: 31708 Plug Co. Name: ENSMINGER-KIMZEY, A GENERAL PARTNERSHIP  
Proposal Rcvd. from: MIKE KIMSEY Company: ENSMINGER-KIMZEY, A GENERA Phone: (620) 852-3456

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED 5 5/8" BORE TO 917'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500. AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE  
Date/Time Plugging Completed: 11/03/2006 1:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

DRILL PIPE WAS RAN INTO THE WELL TO 917'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO 917' THE DRILL PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED  
KCC DISTR.

NOV - 3 2006

CHANUTE, KS

INVOICED

DATE 11-20-06  
INV. NO. 2007060841

Remarks:

Plugged through: DP

District: 03

Signed Clayton P. Titel  
(TECHNICIAN)

RECEIVED Form CP-2/3  
NOV 17 2006  
KCC WICHITA

PPH