

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-00519-00-00
Spot: SWNENE Sec/Twnshp/Rge: 26-17S-25W
4346 4290 feet from S Section Line, 990 feet from E Section Line
Lease Name: ROSS POTTER Well #: 3
County: NESS Total Vertical Depth: 4490 feet

KCC
ajb
Per
ACO-1
G.P.S.
Loc.

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 4489 | | |
| SURF | 8.625 | 237 | | |

\$ 145.93

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2006 4:30 PM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: MARK LIEKER Company: BEREXCO INC. Phone: (785) 628-6101

Proposed Plugging Method: PUMPED 25 SX CMT & 150 HULLS @ 4420'. PLUG AT 3200' WITH 50 SX COMMON 3%CC. PLUG AT 850' WITH 160 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/26/2006 8:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PULLED TUBING TO 3200' & MIXED 50 SX COMMON 3% WAITED 1-1/2 HOURS, PRESSURED CASING TO 500# AND HELD, PERFORATED CASING @ 850' PUMPED 160 SX CMT., DID NOT CIRCULATE, TIED ONTO BACKSIDE AND PUMPED 10 SX CMT. AND PRESSURED TO 500# AND HELD. Topped off with 35 sx cmt.

Perfs:

INVOICED
DATE 11-21-06
INV. NO. 2007060846

Remarks: USED COMMON 3%CC -60/40 POZMIX 6% GEL BY ALLIED CEMENTING

Plugged through: TBG

District: 01

Signed Steve Hunsicker for KCC
(TECHNICIAN)

RECEIVED
NOV 20 2006
KCC WICHITA

Handwritten initials