

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22679-00-00
Spot: NESWNW Sec/Twnshp/Rge: 25-8S-18W
3630 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HAZEN B Well #: 1
County: ROOKS Total Vertical Depth: 3423 feet

Operator License No.: 31824
Op Name: BROWN, THOMAS M.
Address: 403 NW 3RD PO BOX 250
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3410	0	150/300 SX
SURF	8.625	216	0	135 SX

\$ 111.25

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/09/2006 1:00 PM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: THOMAS M. BROWN Company: BROWN, THOMAS M. Phone: (785) 737-7069

Proposed Plugging Method: Ordered 260 sxs 60/40 pozmix - 10% gel - 500# hulls.
4 1/2" casing cemented from 3410' w/450 sxs to surface.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2006 2:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Quality Oil Well Cementing pumped 260 sxs 60/40 pozmix - 10% gel with 500# hulls.
Max. P.S.I. 700#. S.I.P. 500#.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3410	3423	OH	
3350	3135		
3135	3138		
0	0		

INVOICED
DATE 11-21-06
INV. NO. 2007060847

Remarks: QUALITY OIL CEMENTING.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

NOV 13 2006

RECEIVED
Form CP-2/3
NOV 20 2006
KCC WICHITA

PKT

CLASS OIL

210 W. 34TH

HAYS, KS. 67601

CONTR R & C DRILLING

GEOLOGIST ANTHONY KRUSE


#1 'B' HAZEN

CTY ROOKS

FIELD DOPLITA

25-8-18W

NE SW NW



ELV 1992 KB SPD 5/16/85 CARD ISSUED 9/5/85 IP P 9 BO & 38 BWPD

1987 GL DRLG COMP 5/21/85 SHAW (TOR) 3135-3138 OA

API 15-163-22,679 LKC 3312-3350 OA

ARB OH 3410-3418

LOG	Tops	Depth/Datum
ANH	1304+ 688
B/ANH	1342+ 650
TOP	2904- 912
HEEB	3114-1122
TOR	3135-1143
LKC	3155-1163
BKC	3377-1385
ARB	3410-1418
RTD	3415-1423
PBTD	3418-1426
DDTD	3423-1431

8 5/8 " 216 / 135SX, 4 1/2 " 3410 / 450SX
 MICT - CO, (ARB OH), DD 3423 TD, AC 3000G (28% G), SWB
 DWN, SO, PB 3418 TD, PF (LKC) 1 / 3350, AC 750G (15%), SWB
 DWN, SO, PF (LKC) 1 / 3312, AC 750G (15%), SWB DWN, SO, PF
 (TOR) 1 / 3135, 1 / 3138, AC 1500G (28%), SWB DWN, SO, SET
 2 3/8 " TBG AT 3415, POP, P 9 BO & 38 BWPD (GR 34°), 6/4/85,
 COMMINGLED

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS