

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22687-00-01
Spot: S2SWNW Sec/Twnshp/Rge: 15-35S-14W
2970 feet from S Section Line, 660 feet from W Section Line
Lease Name: STATELINE Well #: 1-15
County: BARBER Total Vertical Depth: 4999 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4999	2830	190 SX
SURF	8.625	304		275 SX

\$ 102.47

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/26/2006 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MARVIN MILLER Company: _____ Phone: (620) 532-3628

Proposed Plugging Method: SANDED TO 4731' & PUT 5 SX CMT ON TOP. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/26/2006 5:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4731' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THRU DUMP BAILER. SPOT PLUGS THROUGH 5.5 CASING. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4866	4886		
4850	4858		
4808	4816		
4800	4805		

INVOICED
DATE 11-21-06
INV. NO. 2007060853

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR. RECOVERED 2830' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED Form CP-9/3
NOV 20 2006
KCC WICHITA