

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21377-00-00
Spot: SWSW Sec/Twnshp/Rge: 30-34S-18W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: HUCK Well #: 1
County: COMANCHE Total Vertical Depth: 7000 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6750		
COND	20	64		
PROD	5.5	6998	4250	300 SX
SURF	8.625	640		350 SX

\$ 227.50

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/17/2006 9:40 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: MARVIN MILLER Company: MTM PETROLEUM Phone: (620) 532-3628

Proposed Plugging Method: AS KCC REQUIRES - SAND 6390-5 SXS. PIPE RECOVERY 4250. 900-15 GEL. 50 SXS. 670-50 SXS. 260-40SXS. AO 10SXS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2006 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SANDED TO 6390' & 5 SX CMT. 1ST PLUG AT 900' WITH 15 SX GEL - 50 SX CMT. 2ND PLUG AT 670' WITH 50 SX CMT. 3RD PLUG AT 260' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6938	6944		
6888	6894		
6856	6864		
6440	6448		

INVOICED
DATE 11-21-06
INV. NO. 2007060853

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED CEMENTING CO. INC. RECOVERED 4250' OF 5.5 CASING.

Plugged through: CSG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
NOV 20 2006
KCC WICHITA
Form CR 2/3
[Signature]
PKT