

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21250-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 15-34S-25W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: FRAME GAS UNIT Well #: 2-15
County: CLARK Total Vertical Depth: 5832 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E. CENTRAL, SUITE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	20	55		
PROD	4.5	5720	4250	150 SX
SURF	8.625	806		425 SX

\$ 189.54

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/19/2006 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVE OLLER Company: Phone: (620) 532-9232

Proposed Plugging Method: SANDED TO 5626' WITH 4 SX CMT. PLUG AT 840' WITH 15 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/19/2006 10:45 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED TO 5626 WITH 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 840' WITH 15 SX GEL & 50 SX CMT. CIRCULATE FLUIDS TO SURFACE. 2ND PLUG AT 420' WITH 50 SX CMT. CIRCULATE FLUID TO SURFACE. 3RD PLUG AT 40' WITH 10 SX CMT. CIRCULATE CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5772	5774		SPF
5732	5745		SPF
5715	5719		SPF
5688	5704		SPF
5676	5680		SPF

INVOICED
DATE 11-21-06
INV. NO. 2007060854

Remarks: USED 60/40 POZMIX 6% BY ALLIED. RECOVERED 4250' OF 41/2" CASING.

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
PIRTH (TECHNICIAN)

RECEIVED

NOV 20 2006

KCC WICHITA

Form CP-2/3