

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20161-00-01  
Spot: E2W2W2NE Sec/Twnshp/Rge: 29-30S-18W  
1320 feet from N Section Line, 2130 feet from E Section Line  
Lease Name: COBB A OWWO Well #: 2-29  
County: KIOWA Total Vertical Depth: 5100 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E. CENTRAL, SUITE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	5097	2510	150 SX CMT
SURF	8.625	566		325 SX CMT \$ 165.75
T1	2.375	5051		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2006 1:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: DAVE OLLER Company: \_\_\_\_\_ Phone: (620) 532-9232

Proposed Plugging Method: SANDED TO 5626 WITH 4 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2006 2:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED TO 5626' WITH 4 SX CMT. WITH BAILER. 1ST PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. CIRCULATE FLUID TO SURFACE. 2ND PLUG AT 600' WITH 50 SX CMT. CIRCULATE FLUID TO SURFACE. 3RD PLUG AT 40' WITH 15 SX CMT. CIRCULATE FLUID TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5028	5038		
5012	5024		
5002	5007		

Remarks: USED 60/40 POZMIX 6%. RECOVERED 2510' OF 41/2 CASING.

Plugged through: CSG

District: 01

Signed Jerry W. Stapleton  
PIRT II (TECHNICIAN)

INVOICED  
DATE 11-21-06  
INV. NO. 2007060854

RECEIVED  
NOV 20 2006  
KCC WICHITA

Form CP-2/3

CP PRT