

6- 100512

205  
R

3-31

TO:

API number: 15-141-20,315-00-00

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

W2 SE NE /4 SEC. 26, 10 S, 15 W  
3300 feet from S section line  
990 feet from E section line

Operator license# 05146

Lease Koelling well # 1-26

Operator: Rains & Williamson Oil Co.,

County OB Oak

Address: 220 West Douglas  
Suite 435  
Wichita, Kansas 67202

Well total depth 3400 <sup>110.50</sup> feet  
Conductor Pipe: \_\_\_ inch @ \_\_\_ feet  
Surface pipe 8 5/8 Inch @ 220 feet

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: Duke Drilling Company, Inc. License# 05929

Address: \_\_\_\_\_

Company to plug at: Hour: ?? Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: \_\_\_\_\_

Plugging proposal received from: Galen Roach

Company: Duke Drilling Company, Inc. phone: \_\_\_\_\_

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 980 feet with 25 sacks Rat hole: 15 sacks  
2nd plug @ 570 feet " 100 " Mousehole: \_\_\_ sacks  
3rd plug @ 270 feet " 40 "  
4th plug @ 40 feet " Wiper plug & 10 SX

RECEIVED COMM  
KANSAS CORP COMM  
1996 APR - 3 P 10:27  
4-3-96

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 9:45 am, Day: 31, Month: March, Year: 1996

Actual plugging report: Hole reported plugged as above.  
Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 1820 GL, Anhydrite depth: 978 - 1012 feet Anhy. plug: YES  
Dakota plug: YES Bottom hole plug in place: NO  
Plugged through drill pipe: YES  
Did NOT penetrate Arbuckle, cemented by Allied Cementing

I  did not  observe the plugging.

David K. Wann  
David K. Wann P.I.R.T. II  
(agent)

**INVOICED**  
DATE APR 11 1996  
INV. NO. 45185  
3-31