

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 163 - 21971-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 3/11/83

Well Operator: PRIDE ENERGY COMPANY KCC License #: 32192  
(Owner / Company Name) (Operator's)

Address: PO BOX 701950 City: TULSA

State: OKLAHOMA Zip Code: 74170-1950 Contact Phone: (918) 524 - 9200

Lease: CITY OF STOCKTON Well #: 1-13 Sec. 13 Twp. 7 S. R. 18  East  West

**NE SE - NE - SE** Spot Location / QQQQ County: ROOKS

1720 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

310 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 13-3/8" 48# Set at: 89 Cemented with: 135 Sacks

Surface Casing Size: 8-5/8" 24# Set at: 1284' Cemented with: 475 Sacks

Production Casing Size: 5-1/2" 14# Set at: 3359' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: PERFS @ 3326'-30' (2 SPF)

Elevation: 1882' ( G.L. /  K.B.) T.D.: 3359' PBTD: N/A Anhydrite Depth: 1266'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): SPOT 50 SX CMT. OVER PERFS, SPOT GEL SPACER UP TO 1266', SHOOT 5-1/2" CSG @ 1266', PUMP CEMENT TO FILL CASING TO SURFACE. IF 5-1/2" IS NOT PULLED, PUMP 100 SX AROUND 5-1/2" AND FILL TO SURFACE.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? NO LOGS AVAILABLE. THEY WERE APPARENTLY NEVER RELEASED BY ORIGINAL OPERATOR. MEMOS IN RUPE OIL CO. FILE INDICATE LOGS WERE RUN AND WE ASSUME COPIES WERE SENT TO KCC.

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: LARRY MILLER

Address: PO BOX 701950 Phone: (918) 524 - 9200

City / State: TULSA/OK

Plugging Contractor: TO BE DETERMINED Express Well Service KCC License #: N/A 6426

Address: N/A P.O. Box 19 Phone: (N/A)

Proposed Date and Hour of Plugging (if known?): TO BE DETERMINED

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/08/06 Authorized Operator / Agent: Larry O. Miller  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED**

**NOV 13 2006**

**KCC WICHITA**

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Pride Energy Company, a General Partnership  
Box 701950  
Tulsa, OK 74170

November 21, 2006

Re: CITY OF STOCKTON #1-13  
API 15-163-21971-00-00  
NESENESE 13-7S-18W, 1720 FSL 310 FEL  
ROOKS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely



Barry Metz  
Deputy Director