

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-065-23,224-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR RUSSELL OIL, INC. KCC LICENSE # 3293
(owner/company name) (operator's)

ADDRESS PO Box 1469 CITY Plainfield

STATE Illinois ZIP CODE 60544 CONTACT PHONE # (815) 609-7000

LEASE BOLLIG "C" WELL# 2-25 SEC. 25 T. 10S R. 23 (East/West)

SE - SW - NE SPOT LOCATION/QQQQ COUNTY Graham

2,310 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1,680 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 219' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2,359' KB T.D. 4,055' PBDT _____ ANHYDRITE DEPTH 1,864'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING _____

RECEIVED

NOV 22 2006

(If additional space is needed attach separate page) **KCC WICHITA**

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? To be filed by Operator

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Burton Beery PHONE# (785) 483-3141

ADDRESS PO Box 709 City/State Russell, KS 67665

PLUGGING CONTRACTOR Shields Drilling Co. KCC LICENSE # 5184
(company name) (contractor's)

ADDRESS PO Box 709, Russell, KS 67665 PHONE # (785) 483-3141

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 11-14-06 1:00AM

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT SHIELDS DRILLING CO.

DATE: 11-20-06 AUTHORIZED OPERATOR/AGENT: Burton Beery
(signature)

* Well already plugged - KCC-Dlg

Dist
04

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-065-23,224

LEASE NAME Bollig "C"

WELL NUMBER 2

2,310 Ft. from ^N ~~XX~~ Section Line

1,680 Ft. from ^E ~~XX~~ Section Line

SEC. 25 TWP. 10S RGE. 23 ~~(E)~~ or (W)

COUNTY Graham

Date Well Completed 11-13-06

Plugging Commenced 11-13-06

Plugging Completed 11-14-06

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RUSSELL OIL, INC.

ADDRESS PO BOX 1469, Plainfield, IL 60544

PHONE#(815) 609-7000 OPERATORS LICENSE NO. 3293

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-14-06 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4,055'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	219'	Cmtd. w/175 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Push plug to 1,900', pump 25 sax cement on plug thru drill pipe; push plug to 1,025', pump 100 sax cement on plug thru drill pipe; push plug to 275', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Circ. 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor SHIELDS DRILLING CO. License No. 5184

Address PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RUSSELL OIL, INC.

STATE OF KANSAS COUNTY OF RUSSELL, ss.


BURTON BEERY, DRILLING SUPT.

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed therewith, the same are true and correct, so help me God.

(Signature) Burton Beery
(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 20th day of November, 2006

My Commission Expires: _____



RECEIVED
NOV 22 2006

Contractor KCC WICHITA




Shields

Russell, Kansas

WELL LOG

Operator: Russell Oil, Inc.
 Well: Bollig "C" #2
 Commenced: October 30, 2006
 Completed: November 14, 2006
 Contractor: Shields Drilling Co.

Well Description: 2310' FNL, 1680' FEL
 NE/4 Sec. 25-10S-23W
 Graham Co., KS



Elevation: 2,359' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	219'	Cmted. w/175 sax

..... Figures Indicate Bottom of Formations

Sand & shale	1,240'
Sand	1,520'
Sand & redbed	1,850'
Anhydrite	1,908'
Redbed & shale	2,555'
Shale	3,015'
Shale & lime	3,190'
Lime	4,055' RTD

Notes

RECEIVED
 NOV 22 2006
 KCC WICHITA