

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
D. S. Market, Room 2078  
chita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-141-20,122-00-00

LEASE NAME Greene

WELL NUMBER 1-27

2010 Ft. from S Section Line

1490 Ft. from <sup>NW</sup> Section Line

SEC. 27 TWP. 10S RGE. 15W (E) or (W)

COUNTY Osborne

Date Well Completed \_\_\_\_\_

Plugging Commenced 8-12-98

Plugging Completed 8-14-98

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Graham-Michaelis Corporation

DRESS P.O. Box 247 Wichita, Ks. 67201

PHONE# (316) 264-8394 OPERATORS LICENSE NO. 5134

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3480'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	259'	None
				4-1/2"	3477'	1810'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section. Plugged off bottom with sand to 2950' and 4 sacks cement. Shot pipe loose @1810'. Pulled up to 1475', pumped 70 sks. cement and 300# hulls, pulled to 1025', pumped 35 sks. cement and 100# hulls, pulled up to 575', pumped 35 sks. cement and 100# hulls, pulled up to 150' and circulated 45 sks. to surface. 60/40 pos, 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Graham-Michaelis Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso

(Employee of Operator) or (Operator)

Above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of August, 1998

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

