

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC Per 11/27/06
Per OPS Ftg's
NWSW Senw

API Well Number: 15-055-21299-00-00
Spot: NESWNW Sec/Twnshp/Rge: 6-23S-33W
3820 feet from S Section Line, 4030 feet from E Section Line
3777
Lease Name: CORN GAS UNIT 3914 Well #: 2HI
County: FINNEY Total Vertical Depth: 2807 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2807		425 SX
SURF	8.625	1070		475 SX

91.23

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/02/2006 1:30 PM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: DEANN SMYERS Company: _____ Phone: (281) 366-4395

Proposed Plugging Method: PRODCEDURES APPROVED BY STEVE DURANT (KCC). MIX AND PUMP 300 SACKS OF CEMENT, WITH 500 POUNDS OF COTTONSEED HULLS MIXED IN THE LEAD SLURRY, TO FILL THE 5.5" CASING FROM GROUND LEVEL TO 2620'. CEMENT BLEND TO BE 60/40 CLASS C PREMIUM PLUS W/ 6% GEL, MIXED AT 13.1 PPG, WITH YIELD OF 1.53 CUFT/SX. HAVE 50 EXTRA SACKS OF CEMENT ON LOCATION TO FILL THE ANNULUS BETWEEN THE 8.625" X 5.5" CASING, IF NEEDED. CUT OFF AND CAP THE CASINGS 4' BELOW GROUND LEVEL. RESTORE THE LOCATION.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2006 3:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

MIX & PUMP 500# HULLS IN CMT TO PLUG BOTTOM. MIX & PUMP 267' SX CMT FROM 2600' TO SURFACE. MAXIMUM PRESSURE 250 PSIG. BLEW PRESSURE OFF OF CASING & TOPPED OFF WITH 70 SX. RU TO BACKSIDE MIX & PUMP 20 SX CMT. DOWN BACKSIDE. PRESSURE UP & SI

Perfs:

Top	Bot	Thru	Comments
2600	2620		

INVOICED
DATE 11-28-06
INV. NO. 2007060863

Remarks: USED 60/40 POZMIX 6% W/1%CACL. BY HALLIBURTON SERVICES
Plugged through: CSG

District: 01 Signed Richard W. Lacey for Jim Holland
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA
PKT