

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-20626-00-00  
Spot: SEWNNE Sec/Twnshp/Rge: 21-28S-35W  
3985 feet from S Section Line, 1782 feet from E Section Line  
Lease Name: FRY Well #: 1  
County: GRANT Total Vertical Depth: 3053 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 12950 E. 13TH  
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3046	1942	200 SX
SURF	8.625	1832	0	575 SX

\$ 99.22

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/02/2006 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: STAN MITCHELL Company: \_\_\_\_\_ Phone: (620) 277-2511

Proposed Plugging Method: AS PER KCC - JIM HOLLAND - SET CIBP @ 2885 W/ 2 SKS CMT. RUN FREE POINT-CUT OFF CSG @1800'- RECOVER CSG - RIH W/ TBG- SPOT 1 ST PLUG @ 1850' W/ 50 SKS 60/40 POZ W/ 6 5 GEL - SPOT 2ND PLUG @ 700 WITH 60/40 POZ W/ 65 - SPOT 3RD PLUG @ 60' W/ 60/40 POZ W/ 6 % GE; - CAP OFF 8 5/8'

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/02/2006 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

RU WIRELINE, RIH & SETCIBP @ 2885' W/2 SX CMT ON TOP THRU BAILER. POOH WITH CASING & LAY DOWN. RIH WITH TUBING TO 1870' LOAD HOLE WITH MUD & 50 SX CMT. POOH WITH TUBING TO 700' LOAD HOLE WITH 40 SX CMT. POOH WITH TUBING LEAVE 2 JOINTS IN HOLE LOAD HOLE WITH 20 SX CMT. TO SURFACE

Perfs:

Top	Bot	Thru	Comments
2955	2958		
2931	2935		
2893	2898		

**INVOICED**  
DATE 11-29-06  
INV. NO. 2007060869

Remarks: USED 60/40 6% GEL BY ALLIED. RECOVERED 1942' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed Richard W Lacey for Jim Holland  
(TECHNICIAN)

RT