

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22841-00-00
Spot: S2NWNW Sec/Twnshp/Rgc: 16-22S-11W
4190 feet from S Section Line, 4690 feet from E Section Line
Lease Name: SHEPHERD Well #: 3
County: STAFFORD Total Vertical Depth: 3620 feet

Operator License No.: 5056 •
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3619	1650	150 SX
SURF	8.625	265		160 SX

\$ 117.65

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2006 10:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: _____ Phone: (620) 793-0915

Proposed Plugging Method: SANDED TO 3590' & 5 SX CMT. WITH DUMP BAILER. PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/06/2006 12:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3590' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3544	3548		

INVOICED

DATE 11-29-06
INV. NO. 2007060870

Remarks: USED 60/40 POZMIX 6% GEL BY QUALITY OIL WELL CEMENTING. RECOVERED 1650' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA

PKT