

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-00379-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 3-23S-34W
2640 feet from N Section Line, 2640 feet from W Section Line
Lease Name: ANDERSON A Well #: 1
County: FINNEY Total Vertical Depth: 2662 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2460		
PROD	5.5	2662		400 SX
SURF	8.625	1005		500 SX

\$ 86.52

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/02/2006 11:00 AM

Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES

Proposal Rcvd. from: DEANN SMYERS Company: _____ Phone: (281) 366-2395

Proposed Plugging Method: PER PROCEDURES BY STEVE DURANT (KCC). PULL 3.5" LINER AND BAKER PACKER. SET CIBP (WITH 2 SACKS OF CEMENT ON TOP OF PLUG) AT 2460'. FILL CASING WITH WATER AND RUN CBL TO DETERMINE TOC. CIRCULATE CEMENT DOWN 5.5" CASING, THROUGH CIRCULATING HOLES, AND OUT ANNULUS BETWEEN 8.625" & 5.5" CASINGS. LEAVE ANNULUS AND 5.5" CASING FULL OF CEMENT FROM GROUND LEVEL TO CIRCULATING HOLES. CUT OFF AND CAP CASINGS 5' BELOW GROUND LEVEL. RESTORE LOCATION.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/02/2006 12:30 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

31/2" LINER PULLED OUT OF WELL. CIBP SET @ 2420' W/2 SX CMT ON TOP. CMT BOND SHOWED GOOD CMT TO SURFACE ON 51/2 CASING. PERFORATE 51/2 CASING @ 1420' & ESTABLISH INJECTION RATE. MIX & PUMP 100# HULLS AND 176 SX CMT FROM SURFACE TO 1420' SQUEEZE 20 SX CMT OUTSIDE OF CASING. PRESSURE PEAKED AT 900 PSIG & SI AT 400 PSIG. RU TO BACKSIDE, MIX & PUMP 22 SX CMT DOWN ANNUALS PRESSURE UP & SI

Perfs:

Top	Bot	Thru	Comments
2492	2638		

INVOICED
DATE 11-28-06
INV. NO. 2007060863

Remarks: USED 60/40 POZMIX 6% GEL W/1% CACL BY HALLIBURTON SERVICES

Plugged through: CSG

District: 01

Signed Richard W. Lacey for Jim Holland
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA

PKT