

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21812-00-00
Spot: SENWSW Sec/Twnshp/Rge: 18-23S-33W
1640 feet from S Section Line, 1250 feet from W Section Line
Lease Name: GARDEN CITY 5 GU Well #: 3
County: FINNEY Total Vertical Depth: 3010 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 WEST OKLAHOMA AVENUE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3010		635 SX
SURF	8.625	1137		500 SX
T1	2.375	2835		

\$ 97.83

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/02/2006 9:00 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: DEANN SMYERS Company: _____ Phone: (281) 366-4395

Proposed Plugging Method: MIX AND PUMP 200 SACKS OF CEMENT, WITH 500 LBS OF COTTONSEED HULLS IN THE LEAD SLURRY, TO FILL THE 4.5" CASING FROM GROUND LEVEL TO 2820. PRESSURE CASING TO 300 PSI. CEMENT BLEND: 60/40 CLASS C PREMIUM PLUS W/6% GEL, MIXED AT 13.1 PPG, YEILD 1.64 CUFT/SK. HAVE 50 EXTRA SACKS OF CEMENT ON HAND TO TOP OFF ANNULUS BETWEEN 8.625" X 4.5" CASING. PRESSURE ANNULUS TO 300 PSI. CUT OFF AND CAP CASING 5' BELOW GROUND LEVEL. RESTORE LOCATION.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/02/2006 10:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

MIX & PUMP 500# HULLS WITH CMT DOWN 4 1/2 CASING. MIX & PUMP 200 SX CMT. FROM 2800' TO SURFACE. NO PRESSURE. RU TO BACKSIDE MIX & PUMP 97 SX CMT DOWN ANNUALS, PRESSURE UP & SI. RD OFF WELL & MOVE TO NEXT WELL 4PM RU & TOP OFF WELL WITH 6 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2800	2820		

INVOICED
DATE 11-28-06
INV. NO. 2007060863

Remarks: USED 60/40 POZMIX 6% GEL BY HALIBURTON SERVICES

Plugged through: CSG

District: 01

Signed Richard W. Lucy for Jim Holland
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA

PKT