

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20605-00-00 01 PRT
Spot: SWNESE Sec/Twnshp/Rge: 33-21S-14W
1550 feet from S Section Line, 990 feet from E Section Line
Lease Name: ELINOR KRAMPE Well #: 2
County: STAFFORD Total Vertical Depth: 3860 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 8223 WILLOW PLACE SOUTH
HOUSTON, TX 77070

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3832	350	CASING WAS ATE UP.
SURF	8.625	298		250 SX
T1	2.875	3660		

\$125.45

Well Type: OTC EOR PRT UIC Docket No: E17848.2 Date/Time to Plug: 10/27/2006 2:10 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JEFF TEARE Company: Phone: (281) 517-7199

Proposed Plugging Method: CIBP@3500' W/2 SX CMT. RUN TUBING TO 720' COULDN'T GET ANY FARTHER IN HOLE, PUMPED 350 SX CMT & CIRCULATED TO SURFACE, PULLED TUBING & TOPPED OFF WITH 35 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2006 3:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP@3500' W/2 SX CMT. RUN TUBING TO 720' COULDN'T GET ANY FARTHER IN HOLE, PUMPED 350 SX CMT & CIRCULATED TO SURFACE, PULLED TUBING & TOPPED OFF WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3617	3622		
3592	3600		
3555	3560		

INVOICED
DATE 11-28-06
INV. NO. 2007060865

Remarks: USED 60/40 6% GEL BY COPELAND. RECOVERED 350' OF 5 1/2" OF CASING.

Plugged through: TBG

District: 01

Signed Richard M. Lacey for Michael Maier
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA

PRT