

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC 11/27/06
PKT per FTGS
to PSD.
API Well Number: 15-145-21497-00-00
Spot: NZNE
Pawnee

Sec/Twnshp/Rge: 28-22S-17W
4047 ~~660~~ feet from N Section Line, 1320 feet from E Section Line
Lease Name: BARGER 1456 Well #: 1-28
County: PAWNEE Total Vertical Depth: 4190 feet

Operator License No.: 32566
Op Name: CLEARY PETROLEUM CORPORATION
Address: 2601 NW EXPRESSWAY SUITE 801W
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4163	1821	200 SX
SURF	8.625	822		500 SX

\$ 136.18

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/15/2006 8:00 AM
Plug Co. License No.: 32566 Plug Co. Name: CLEARY PETROLEUM CORPORATION
Proposal Rcvd. from: GEORGE MOORE Company: _____ Phone: (620) 886-2038

Proposed Plugging Method: SET CIBP AT 3950' WITH 2 SX CMT. 1821' OF 4 1/2". SPOTTED PLUGS THROUGH CASING. PLUG AT 1050' WITH 15 SX GEL - 15 SX CMT. PLUG AT 850' WITH 50 SX CMT. PLUG AT 400' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2006 10:15 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP AT 3950' WITH 2 SX CMT. 1821' OF 4 1/2". SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 1050' WITH 15 SX GEL - 15 SX CMT. 2ND PLUG AT 850' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 40 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4088	4120		

INVOICED
DATE 11-28-06
INV. NO. 2007060866

Remarks: USED 60/40 POZMIX 6% GEL BY ALIED. RECOVERED 1821' OF 4 1/2"

Plugged through: TBG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA

PKT