

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC Pkt
11-27-06
per GPS Pkgs.

API Well Number: 15-175-00464-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 3-31S-33W
~~2640~~ feet from N Section Line, ~~2640~~ feet from W Section Line
Lease Name: HOPKINS ESTATE UNIT 2432 Well #: 1
County: SEWARD Total Vertical Depth: 2810 feet

Operator License No.: 5208
Op Name: EXXONMOBIL OIL CORP
Address: 14950 HEATHROW FORREST PARKWA
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	2775		1000 SX CMT
SURF	10.75	705		400 SX CMT

\$ 91.33

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/02/2003 1:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: RICHARD LEWIS Company: _____ Phone: (316) 544-5534

Proposed Plugging Method: RIH W/WIRELINE & TAG BOTTOM 2544' PERFS ARE SANDED OFF DUE TO CASING LEAK. TOP OF FLUID @ APPROX. 370' RIH WITH 23/8" TUBING TO 2500' MIX & PUMP 300# HULL WITH 35 SX CMT & DISPLACE TO BOTTOM WITH MUD. POOH WITH TUBING & LAY DOWN.RU & PULL STRETCH ON 65/8" CASING. NO STRECTH. FOUND CMT IN 65/8"X103/4" ANNULUS AT SURFACE. RIH WITH TUBING TO 1700' LOAD HOLE WITH 35 SX CMT. POOH WITH TUBING TO 730' LOAD HOLE WITH 45 SX CMT. POOH WITH TUBING TO 60' LOAD HOLE WITH 20 SX CMT. TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/02/2006 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

RIH W/WIRELINE & TAG BOTTOM 2544' PERFS ARE SANDED OFF DUE TO CASING LEAK. TOP OF FLUID @ APPROX. 370' RIH WITH 23/8" TUBING TO 2500' MIX & PUMP 300# HULL WITH 35 SX CMT & DISPLACE TO BOTTOM WITH MUD. POOH WITH TUBING & LAY DOWN.RU & PULL STRETCH ON 65/8" CASING. NO STRECTH. FOUND CMT IN 65/8"X103/4" ANNULUS AT SURFACE. RIH WITH TUBING TO 1700' LOAD HOLE WITH 35 SX CMT. POOH WITH TUBING TO 730' LOAD HOLE WITH 45 SX CMT. POOH WITH TUBING TO 60' LOAD HOLE WITH 20 SX CMT. TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2599	2716		

INVOICED
DATE 11-28-06
INV. NO. 2007660867

Remarks: USED COMMON BY SARGENT & HORTON PLUGGING

Plugged through: TBG

District: 01

Signed Richard W. Lacey for Jim Holland
(TECHNICIAN)

RECEIVED Form CP-2/3
NOV 22 2006
KCC WICHITA

Pkt