

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC Pkt 11/27/06
per CPS Figs.

API Well Number: 15-189-20633-00-00

Spot: SESENWNW

Sec/Twnshp/Rge: 11-35S-39W

4042 ~~1250~~ feet from X Section Line, ~~1250~~ feet from X Section Line

Lease Name: DORTH-EHRHARDT UNIT Well #: 1

County: STEVENS

Total Vertical Depth: 3160 feet

Operator License No.: 5208

Op Name: EXXONMOBIL OIL CORP

Address: 14950 HEATHROW FORREST PARKWA
HOUSTON, TX 77210

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3141		655 SX CMT
SURF	8.625	591		260 SX CMT

\$102.70

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/23/2006 10:00 AM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: RICHARD LEWIS

Company:

Phone: (316) 544-5534

Proposed Plugging Method: RU TO 5 1/2" CASING, MIX & PUMP 400# HULLS & 25 SX CMT. TO PLUG BOTTOM. DISPLACE WITH MUD TO BOTTOM. MUD SPACER TO 650', MIX & PUMP 80 SX CMT. FROM 650' TO SURFACE. PRESSURE UP & SI. RU TO BACKSIDE, MIX & PUMP 20 SX DOWN BACKSIDE, PRESSURE UP & SI

Plugging Proposal Received By: RICHARD LACEY

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/23/2006 1:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

RU TO 5 1/2" CASING, MIX & PUMP 400# HULLS & 25 SX CMT. TO PLUG BOTTOM. DISPLACE WITH MUD TO BOTTOM. MUD SPACER TO 650', MIX & PUMP 80 SX CMT. FROM 650' TO SURFACE. PRESSURE UP & SI. RU TO BACKSIDE, MIX & PUMP 20 SX DOWN BACKSIDE, PRESSURE UP & SI

Perfs:

Top	Bot	Thru	Comments
2967	3042		

INVOICED

DATE 11-28-06

INV. NO. 2007060867

Remarks: USED COMMON BY SARGENT & HORTON.

Plugged through: CSG

District: 01

Signed Richard M. Lacey for Jim Holland
(TECHNICIAN)

RECEIVED
Form CP-2/3
NOV 22 2006
KCC WICHITA

PRT