

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

KCC PKT 11/27/06
 per GPS Ptg's

API Well Number: 15-055-00163-00-00

Spot: NE Swne

Sec/Twnshp/Rge: 32-21S-32W

3929

1320 feet from N Section Line,

1320 feet from E Section Line

Lease Name: J E GREATHOUSE

1428 Well #: 1-32

County: FINNEY

Total Vertical Depth: 2750 feet

Operator License No.: 32334

Op Name: CHESAPEAKE OPERATING, INC.

Address: PO BOX 18496 6200 N WESTERN AVE.
OKLAHOMA CITY, OK 73154

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1000		
PROD	5.5	2750		300 SX CMT
SURF	8.625	373		200 SX CMT

\$ 89.38

Well Type: GAS

UIC Docket No:

Date/Time to Plug:

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: BUD NEFF

Company:

Phone: (620) 277-0803

Proposed Plugging Method: BOTTOM IS PLUGGED OFF WITH SAND DUE TO A CSG LEAK. CIBP C/O 1000'. TEST CSG TO 700#. PERF 4 HOLES C/O 975'. ESTABLISH PUMP RATE C/O 600# WITH NO BLOW OR CIRCULATATION OUT ANNULUS. ALLIED PUMPED 80 SX CMT, 100 HULLS THEN 85 SX CMT @600#. SI C/O 75# PUMP 175 SX DOWN 51/2X85/8 ANNULUS. SI C/O 100# HOOK UP TO 5 1/2 CSG. PUMP 5 SX & PRESSURE TO 575# HOLDING.

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/02/2006 11:00 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

BOTTOM IS PLUGGED OFF WITH SAND DUE TO A CSG LEAK. CIBP C/O 1000'. TEST CSG TO 700#. PERF 4 HOLES C/O 975'. ESTABLISH PUMP RATE C/O 600# WITH NO BLOW OR CIRCULATATION OUT ANNULUS. ALLIED PUMPED 80 SX CMT, 100 HULLS THEN 85 SX CMT @600#. SI C/O 75# PUMP 175 SX DOWN 51/2X85/8 ANNULUS. SI C/O 100#,HOOK UP TO 5 1/2 CSG. PUMP 5 SX & PRESSURE TO 575# HOLDING.

Perfs:

Top	Bot	Thru	Comments
2667	2693		

INVOICED
 DATE 11-28-06
 INV. NO. 2007010864

Remarks: USED 60/40 POZMIX 6% BY ALLIED

Plugged through: CSG

District: 01

Signed *Ken Jehlik*
 (TECHNICIAN)

RECEIVED Form CP-2/3

NOV 22

KCC WICHITA

PKT