

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20686-00-01
Spot: SENESE Sec/Twnshp/Rge: 10-29S-41W
1350 feet from S Section Line, 330 feet from E Section Line
Lease Name: COCKREHAM Well #: 10-1
County: STANTON Total Vertical Depth: 6020 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: ATTN: REGULATORY GROUP PO BO
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	5455 <u>5990</u>	165	920 SX
SURF	8.625	1650		550 SX
	<u>Cond 20.00</u>	<u>40</u>		<u>4 yards</u>
	<u>CIBP</u>	<u>5460</u>		<u>1 SX</u>
	<u>CIBP</u>	<u>5517</u>		<u>1 SX</u>

Per RBDms

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/31/2006 10:00 AM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON

Company:

Phone:

\$195.65

Proposed Plugging Method: 400# HULLS & 25 SX PORTLAND COMMON. PUMPED THE FOLLOWING DOWN 51/2 CASING. 25 SX PORTLAND COMMON C/O 1340' IN 51/2 CSG. 20BBL MUD SPACER. 25 SX PORTLAND COMMON C/O 250' IN 51/2 CSG. 2 BBL MUD SPACER. WELL PRESSURED TO 1500#. COULD NOT PUMP PLUGS TO DESIRED SPOT. PULLED 165' OF 51/2 CSG OUT. CMT FROM 250' PLUG IS OVER THE 51/2 STUB 10 SX PORTLAND COMMON C/O 40 TO 0 IN 85/8 CSG.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/01/2006 10:00 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

400# HULLS & 25 SX PORTLAND COMMON. PUMPED THE FOLLOWING DOWN 51/2 CASING. 25 SX PORTLAND COMMON C/O 1340' IN 51/2 CSG. 20BBL MUD SPACER. 25 SX PORTLAND COMMON C/O 250' IN 51/2 CSG. 2 BBL MUD SPACER. WELL PRESSURED TO 1500#. COULD NOT PUMP PLUGS TO DESIRED SPOT. PULLED 165' OF 51/2 CSG OUT. CMT FROM 250' PLUG IS OVER THE 51/2 STUB, 10 SX PORTLAND COMMON C/O 40 TO 0 IN 85/8 CSG.

Perfs:

Top	Bot	Thru	Comments
5318	5440		
<u>5327</u>	<u>5337</u>		
<u>5470</u>	<u>5480</u>		
<u>5318</u>	<u>5440</u>		

INVOICED
DATE 11-29-06
INV. NO. 2007060871

Remarks: USED PORTAND COMMON BY SARGENT & HORTON. RECOVERED 165' OF 51/2" CASING

Plugged through: CSG

District: 01

Signed

(TECHNICIAN)

RECEIVED Form CP-2/3

NOV 22 2006

KCC WICHITA

PKT