

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20382-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 17-34S-29W
2985 feet from S Section Line, 4703 feet from E Section Line
Lease Name: ADAMS RANCH Well #: 1-17R
County: MEADE Total Vertical Depth: 6295 feet

Operator License No.: 30604
Op Name: RAYDON EXPLORATION, INC.
Address: 9400 N. BROADWAY #400
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	6254	4350	200 SX CMT.
SURF	8.625	1532		900 SX

\$ 204.59

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/16/2006 11:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: DAVID RICE Company: _____ Phone: (620) 624-0156

Proposed Plugging Method: DUMP 25 SX CEMENT ON PLUG, SHOOT OFF CASING AT +4000', PULL TO 1560', PUMP 50 SX, PULL TO 500', PUMP 40 SX, PULL TO 40', PUMP 20 SX, 60/40 POZ, 6% GEL.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2006 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

MIX & PUMP 300# HULLS & 25 SX CMT. DISPLACE WITH MUD PRESSURE TO 500 PSIG & SI. RU & PULL STRETCH ON CASING. SHOOT OFF @ 4350', POOH TO 1575' LOAD HOLE WITH 50 SX CMT. POOH WITH CASING TO 600' LOAD HOLE WITH 50 SX CMT. POOH TO 40' LOAD HOLE WITH 10 SX CMT. TO SURFACE

Perfs:

Top	Bot	Thru	Comments
6182	6187		

INVOICED

DATE 11-29-06
INV. NO. 2007060878

Remarks: USED COMMPN BY SARGENT & LILLARD PLUGGING. RECOVERED 4350' OF 41/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W Lacey for Jim Holland
(TECHNICIAN)

[Handwritten Signature]