

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20870-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 1-29S-41W
322 feet from S Section Line, 5092 feet from E Section Line
Lease Name: RICHARD ARNOLD Well #: 1-1
County: STANTON Total Vertical Depth: 5675 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: ATTN: REGULATORY GROUP PO BO
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	13.38	760		600 SX
PROD	5.5	5630		900 SX
SURF	8.625	1891		1500 SX

\$ 184.44

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/06/2006 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: ROGER NORTHCUTT Company: _____ Phone: (620) 492-1435

Proposed Plugging Method: MIX & PUMP 250# HULLS WITH 25 SX CMT. PLUG AT 1900' WITH 25 SX CMT. PLUG AT 700' WITH 25 SX CMT. PLUG AT 100' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2006 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

MIX & PUMP 250# HULLS WITH 25 SX CMT. MUD SPACER TO 1900' WITH 25 SX CMT. LOAD HOLE TO SURFACE & PRESSURE TO 500 PSIG & SI. SDFN. RIH WITH TUBING TO 700' WITH 25 SX CMT. POOH WITH TUBING TO 100' WITH 10 SX CMT. HOOK UP TO BACKSIDE WITH 20 SX CMT. & PRESSURE TO 300 PSIG & SI

Perfs:

Top	Bot	Thru	Comments
5460	5484		

INVOICED
DATE 11-29-06
INV. NO. 2007060871

Remarks: USED COMMON BY SARGENT & HORTON PLUGGING

Plugged through: TBG

District: 01

Signed Richard W Lacey for Jim Holland
(TECHNICIAN)

PKS