

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20305-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 19-21S-17W  
1342 feet from S Section Line, 3411 feet from E Section Line  
Lease Name: BEER Well #: 1  
County: PAWNEE Total Vertical Depth: 2070 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 505 S. BROADWAY #200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2059		150 SX
SURF	7	305		175 SX

\$ 67.28

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2006 9:30 AM  
Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC  
Proposal Rcvd. from: BILL TATRO Company: \_\_\_\_\_ Phone: (620) 727-1948

Proposed Plugging Method: SET CIBP @ 1970' & 2 SX CMT. WITH DUMP BAILER. PERFORATED 41/2 @ 1075'. PUMPED 25 SX CMT DOWN 41/2 @ 800 PSIG. HAD INSTANT CMT RETURNS. SHALLOW LEAK. PERFORATED 41/2 @ 400'. RANTUBING TO 1080'. PUMPED 200 SX CMT. CIRCULATED CMT TO SURFACE UP 7"X41/2" ANNULAS.PULLED TUBING. TOPPED OFF HOLE WITH 25 SX CMT PRESSURED HOLE TO 400 PSIG.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2006 10:55 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 1970' & 2 SX CMT. WITH DUMP BAILER. PERFORATED 41/2 @ 1075'. PUMPED 25 SX CMT DOWN 41/2 @ 800 PSIG. HAD INSTANT CMT RETURNS. SHALLOW LEAK. PERFORATED 41/2 @ 400'. RANTUBING TO 1080'. PUMPED 200 SX CMT. CIRCULATED CMT TO SURFACE UP 7"X41/2" ANNULAS.PULLED TUBING. TOPPED OFF HOLE WITH 25 SX CMT PRESSURED HOLE TO 400 PSIG.

Perfs:

Top	Bot	Thru	Comments
2057	2070		

**INVOICED**  
DATE 11-29-06  
INV. NO. 2607060872

Remarks: USED 60/40 6% GEL BY COPELAND SCID

Plugged through: TBG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

PKT