

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20318-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 20-21S-17W  
2327 feet from S Section Line, 5078 feet from E Section Line  
Lease Name: YOUNG Well #: 1  
County: PAWNEE Total Vertical Depth: 2052 feet

Operator License No.: 32302  
Op Name: KEY GAS CORP.  
Address: 505 S. BROADWAY #200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2051		100 SX
SURF	7	759		250 SX

\$ 60.69

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/30/2006 11:30 AM

Plug Co. License No.: 33695 Plug Co. Name: MID-KAN WELL SERVICE, LLC

Proposal Rcvd. from: BILL TATRO Company: \_\_\_\_\_ Phone: (620) 727-1948

Proposed Plugging Method: SET CIBP @ 2002 & 2 SX CMT. WITH DUMP BAILER. PERFORATED 4 1/2" @ 51130'. PUMPED 275 SX CMT DOWN 4 1/2" CIRCULATING CMT. TO SURFACE UP 7" X 4 1/2" ANNUALS-SHUT IN ANNULAS & PRESSURE SYSTEM TO 500 PSIG SHUT IN PRESSURE = 500 PSIG

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/30/2006 11:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2002 & 2 SX CMT. WITH DUMP BAILER. PERFORATED 4 1/2" @ 51130'. PUMPED 275 SX CMT DOWN 4 1/2" CIRCULATING CMT. TO SURFACE UP 7" X 4 1/2" ANNUALS-SHUT IN ANNULAS & PRESSURE SYSTEM TO 500 PSIG SHUT IN PRESSURE = 500 PSIG

Perfs:

Top	Bot	Thru	Comments
2017	2031		

**INVOICED**  
DATE 11-29-06  
INV. NO. 2007060872

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND

Plugged through: CSG

District: 01

Signed Richard Lacey  
(TECHNICIAN)

PLS