

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20222-00-00
Spot: SENENW Sec/Twnshp/Rge: 26-30S-34W
4447 feet from S Section Line, 2863 feet from E Section Line
Lease Name: LIZ SMITH Well #: 1-A
County: HASKELL Total Vertical Depth: 3050 feet

Operator License No.: 5089
Op Name: LEBOSQUET, JOHN W.
Address: 535 S. EMPORIA, SUITE 103
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3048		600 SX
SURF	8.625	706		375 SX

\$ 99.13

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/30/2006 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: RON JOHNSON Company: _____ Phone: (316) 264-6722

Proposed Plugging Method: 35 SX CMT DOWN 2 3/8 TBG. PERF-TECH SHOT 2 3/8 TBG OFF C/O 1120'. TOO H W/TBG PERF-TECH SET 4 1/2" CIBP C/O 1105' PRESSURE TEST CSG TO 750#. HOLDING PERF-TECH PERFORATE 4 HOLES C/O 750'. PRESSURE CSG TO 1600PSI. COULD NOT PUMP INTO PERFS. TIH W/ TBG TO 851'. FILL 4 1/2 CSG WITH CMT IN TWO STAGES USING 75 SX 60/40 POZMIX 6% GEL HOLE STAYED FULL. HOOK UP TO 4 1/2 X 8 5/8 ANNULUS & PUMP 15 SX. PRESSURE TO 800#. HOLDING 600#.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2006 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

35 SX CMT DOWN 2 3/8 TBG. PERF-TECH SHOT 2 3/8 TBG OFF C/O 1120'. TOO H W/TBG PERF-TECH SET 4 1/2" CIBP C/O 1105' PRESSURE TEST CSG TO 750#. HOLDING PERF-TECH PERFORATE 4 HOLES C/O 750'. PRESSURE CSG TO 1600PSI. COULD NOT PUMP INTO PERFS. TIH W/ TBG TO 851'. FILL 4 1/2 CSG WITH CMT IN TWO STAGES USING 75 SX 60/40 POZMIX 6% GEL HOLE STAYED FULL. HOOK UP TO 4 1/2 X 8 5/8 ANNULUS & PUMP 15 SX. PRESSURE TO 800#. HOLDING 600#.

Perfs:

Top	Bot	Thru	Comments
2728	2768		
2678	2700		
2650	2660		
2606	2630		

INVOICED
DATE 11-29-06
INV. NO. 2007060873

Remarks: USED 60/40 POZMIX 6% GEL BY JET STAR.

Plugged through: TBG

District: 01

Signed Ken Jehlik
(TECHNICIAN)

[Handwritten initials]