

4-041985

E-26,839

8-12

API Number: 15-141-20,176-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

20' W. of
NE NW SW / 4 SEC. 27, 10 S, 15 W
2290 feet from S section line
4310 feet from E section line

Operator license# 5134

Lease: Greene Well # 5-27

Operator: Graham Michaelis Corporation

County: Osborne

112.13

Address: P.O. Box 247
Wichita, Kansas 67201

Well total depth 3450 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 248 Feet
W/170 sxs cmt.

Aband. oil well, Gas well, Input well ☒, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 12 Month: August Year 1998

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage

Phone: -

Were: 4 1/2" casing set at 3449' w/200 sxs cement. Perfs at 2746' - 3359'.

D.V. Casing bond log verified cement behind pipe from surface to 1050' plus 2200' down to T.D. Pulled injection string prior to plugging - perf open.
Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [], Part [☒], None []

Completed: Hour: 5:00 P.M., Day: 12, Month: August, Year: 1998

Actual plugging report: Squeezed 4 1/2" casing with 125 sxs 60/40 pozmix - 10% gel with 400# hulls mixed in cement. Max. P.S.I. 500#. S.I.P. 450#.
Checked 8 5/8" S.P. Cement visible at surface in braden head.

Remarks: Cemented by Allied of Russell, Kansas

Condition of casing(in hole): GOOD - BAD Anhy.plug: YES ☒ NOBottom plug(in place): YES, CALC, NO Dakota plug: YES ☒ NO

Plugged through TUBING CASING Elevation: G.L.

I did [☒] / did not [] observe the plugging.

Dennis L Hamel
(agent)

Form CP-2/3

INVOICED

DATE 10-2-98

51404