

4-070108

8-24

API Number: 15-141-20,170 100-06

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C W2 _____ /4 SEC. 27, 10 S, 15 W
2690 _____ feet from S section line
3790 _____ feet from E section line

Operator license# 5134

Lease: Greene Well # 4-27

Operator: Graham-Michaelis Corporation

County: Osborne 111.48

Address: P.O. Box 247
Wichita, Kansas 67201

Well total depth 3430 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 248 feet
W/175 sxs.

ABAND. oil well , Gas well _____, Input well _____, SWD. _____, D&A _____

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kasnas 67524

Company to plug at: Hour: 2:30 P.M. Day: 24 Month: August Year: 1998

Plugging proposal received from: David Patterson

Company: Graham-Michaelis Corporation Phone: 785-483-3136

Were: 4 1/2" set at 3429' w/175 sxs.
Dakota 297' - 547'. Anhydrite 973' - 1005'.
Salt 1346' - 1461'. Perfs. 3351' - 3382'.
Ordered 190 sxs 60/40 pozmix - 10% gel with 500# hulls.

RECEIVED
KANSAS CORPORATION COMMISSION
8-31-98
AUG 31 1998

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part [] , None []

Completed: Hour: 6:00 P.M. Day: 24 , Month: August , Year: 1998

Actual plugging report: Sanded back to 3300' w/4 sxs cement on top. Shot 4 1/2" casing off at 1803'. Pulled to 1475'. Allied pumped 50 sxs 60/40 pozmix - 10% gel w/150# hulls. Pipe stuck. Shot off at 1200'. Pulled 4 1/2" to 1025'. Allied pumped 50 sxs w/100# hulls. Pulled to 575'. Allied pumped 35 sxs w/50# hulls. Pulled to 150'. Allied pumped 55 sxs cement circulated. Hole stayed full.

Remarks:

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____ , NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____ , CASING . Elevation: 1847 GL

I did / did not [] observe the plugging.

Richard Williams
(agent)

Form CP-2/3

INVOICED

DATE SEP 01 1998

INV. NO. 51234