

4-041983

8-14

API Number: 15-141-20,122-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

W2 NE SW /4 SEC. 27, 10 S, 15 W  
2010 feet from S section line  
1490 feet from W section line

Operator license# 5134

Lease: Greene Well # 1-27

Operator: Graham Michaelis Corporation

County: Osborne 113.10

Address: P.O. Box 247  
Wichita, Kansas 67201

Well total depth 3480 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface Pipe: 8 5/8 Inch 259 Feet  
W/175 sxs cmt.

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00 A.M. Day: 13 Month: August Year 1998

Plugging proposal received from: Mike Kelso

Company: Mike's Testing and Salvage Phone: -

Were: 4 1/2" casing set at 3479' w/200 sxs cement. Perfs at 3033' - 3082'.  
Sanded 2950' w/4 sxs cement at top.  
Ordered 150 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis Hamel  
Plugging operations attended by agent? All [ ], Part [ X ], None [ ]

Completed: Hour: 5:00 P.M., Day 14, Month: August, Year: 1998

Actual plugging report: Shot casing at 1810' and pulled to 1475'. Pumped 70 sxs cement with 300# hulls. Pulled to 1025' and pumped 35 sxs cement with 100# hulls. Pulled to 575' and pumped 35 sxs cement with 100# hulls. Pulled to 150' and circulated with cement at surface with 45 sxs cement. Pulled casing with cement in cellar.

Remarks: Cemented by Allied of Russell, Kansas  
Condition of casing(in hole): GOOD \_\_\_ BAD \_\_\_ Anhy.plug: YES \_\_\_ X \_\_\_ NO \_\_\_  
Bottom plug(in place): YES \_\_\_ , CALC \_\_\_ , NO \_\_\_ Dakota plug: YES \_\_\_ X \_\_\_ , NO \_\_\_  
Plugged through TUBING \_\_\_ CASING \_\_\_\_\_. Elevation: \_\_\_\_\_ G.L.

I did [ X ] / did not [ ] observe the plugging.

*Dennis L. Hamel*  
(agent)

Form CP-2/3

INVOICED

DATE 10-2-98  
51405

10-1-98  
Received  
10-5-98