

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67702

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-051-05804-0000

Lease Name Bemis

WELL NUMBER 1

2310 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 22 TWP. 11S RGE. 17W (E) or (W)

COUNTY Ellis

Date well completed 1/13/38

Plugging Commenced 10/31/06

Plugging completed 11/2/06

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Herman L. Loeb

Address P. O. Box 524 Lawrenceville, IL 62439

Phone ( 618 ) 943-2227 OPERATORS LICENSE NO. 3273

Character of Well Oil  
Oil, Gas, D&A, SWD, Input, Water Supply Well)

KCC PKT  
12/1/06 per  
CP-1

The plugging proposal was approved on Sept 2006 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, IS well log attached?

Producing Formation Arbuckle Depth to Top 3397 Bottom 3412 T.D. 3412

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				15"	100'	0'
				10"	1117'	0'
				7"	3397'	0'
				4 1/2"	3397'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, State the character of same and depth placed, from feet to feet each set  
Perforated 2 shots/ft @ 675', 1150' & 1675'. Ran tubing to 2076', pumped 200 sk 60/40 pozmix w/ 10% gel & 700# of cottonseed hulls down tubing and circulated cement to the surface inside & outside of 4 1/2" casing. Pulled tubing, hook up to 4 1/2" casing & pumped 60 sk of cement with 100# of hulls down 4 1/2" casing. All this was done on 11/1/06. On 11/2/06 cement was at the surface inside and outside the 4 1/2" casing.

Name of Plugging Contractor Chito's Well Service License No. 32028

Address 1312 S. Washington, Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman L. Loeb

STATE OF Illinois COUNTY OF Lawrence '33.


George A. Payne (Employee of operator) or (Operator) of the of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the that the same are true and correct, so help me God. (Signature) George A. Payne

(Address) P O Box 743 Newburgh, IN 47629-0743

Subscribed and sworn to before me this 21 day of November 2006

My commission expires: 4/6/10

Donna Carlene Lucas  
Notary Public Donna Carlene Lucas



Form CP-4

RECEIVED

NOV 27 2006

KCC WICHITA