


15-141-00025-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Osborne County. Sec. 35 Twp 10 S. Rge. 15 (E) (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW NW NW
Lease Owner Musgrove Petroleum Corporation, Inc.
Lease Name Worley Well No. 1
Office Address 407 KFH Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed February 24 19 52
Application for plugging filed February 24 19 52
Application for plugging approved February 24 19 52
Plugging commenced February 24 19 52
Plugging completed February 24 19 52
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3553 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface casing				8-5/8"	226'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set bottom plug at 210' w/ 1/2 sack hulls and 15 sacks cement through drill pipe.
Set top plug at 35' w/ 1/2 sack hulls and 10 sacks cement.

Received
3-19-52


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Duke & Wood Drilling Company, Inc.
Address P. O. Box 194, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
GORDON L. KOELLING (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
407 KFH Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of March 19 52

My commission expires July 9, 1952. Notary Public.



15-14/00025-00-00

WELL LOG
Worley #1
SW NW NW Section 35-10S-15W
Osborne County, Kansas

Started February 11, 1952
Completed February 24, 1952

8 5/8" pipe set @ 226'

0-25	Surface clay and post rock
25-85	Sand, shale and post rock
85-95	Sand
95-226	Shale and clay
226-275	Shale and clay
275-315	Sand
315-445	Shale and clay
445-467	Iron & dakota sand
467-610	Sand, clay and shale
610-895	Red bed
895-928	Anhydrite
928-1350	Shale, shells and salt
1350-1525	Shale, shells and salt
1525-1807	Broken lime
1807-2100	Broken lime
2100-2520	Lime and shale
2520-2725	Lime and shale
2725-2940	Lime
2940-3065	Lime
3065-3190	Lime
3190-3325	Lime
3325-3375	Lime
3375-3430	Conglomerate & chert
3430-3465	Conglomerate & chert
3465-3530	Lime and shale
3530-3553	Lime, shale & artbuckle
3553	ROTARY TOTAL DEPTH

A F F I D A V I T

STATE OF Kansas, COUNTY OF Barton 2SS

I, Lynn O. Duke of the DUKE & WOOD DRILLING COMPANY, INC. being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Lynn O. Duke
Vice - President

Subscribed and sworn to before me this 29th day of February 1952.

Dean L. Cooley
Notary Public

My commission expires: April 29, 1953.

Received
3-19-52

PLUGGING
FILE SEC-35T 10 R (SW)
PAGE 147 LINE 10