

15-141-00014-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR


FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Osborne County. Sec. 34 Twp. 10 Rge. 15 (W)  
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE SE NW  
Lease Owner. Sohio Petroleum Company  
Lease Name. Worley Well No. #1  
Office Address. Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole  
Date well completed. Feb. 3, 1949 19  
Application for plugging filed. Feb. 3, 19 49  
Application for plugging approved. 19  
Plugging commenced. Feb. 3 19 49  
Plugging completed. Feb. 3 19 49  
Reason for abandonment of well or producing formation. Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production ..... 19  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. C. D. Steugh  
Producing formation. Arbuckle Depth to top. 3443 Bottom. 3480 Total Depth of Well. 3480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Shale & Shells		100	200	13 3/8"	198'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from ..... feet to ..... feet for each plug set.

3480' to 195' Heavy Mud  
195' to 170' 20 Sacks Cement  
170' to 20' Heavy Cement  
20' to 5' 15 Sacks Cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Sohio Petroleum Company  
Address. P. O. Box 671, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.  
J. H. Bond (employee of owner) or (owner/oper) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Bond


(Address) Feb. 19 49  
Russell, Mo

SUBSCRIBED AND SWORN TO before me this ..... day of ..... 19 49

My Commission Expires July 2, 1949

Notary Public.

21-543-s 8-45-6M



**CONTRACTOR'S VERIFIED LOG**

Operator SONIC PETROLEUM COMPANY Farm Name WORLEY Well No. 31 #1  
 Location NE SE NW Section 34-10-15  
 Pool Name Wildcat County Osborne State Kansas  
 Commencement Date 1-17-49 Completion Date 2/5/49

LOG OF WELL

Depth		Formation	Deviation from Vertical (Degrees)	Remarks
From	To			
0	8	Rig		
8	10	Cellar		
100	200	Shale & Shells		5 5/8 Casing Set at 190 Ft. & cement with 200 sacks cement
200	275	Shale	3yfe	
275	350	Sand		
350	400	Shale		
400	520	Sand	500'	
520	600	Shale & Shells		
600	935	Red Bed & Shale		
935	1000	Anhydrite	1000'	
1000	1700	Shale & Shells	1500'	
1700	1820	Brk. Lime		
1820	2000	Shale & Shells	2000'	
2000	2300	Brk. Lime		
2300	2720	Shale & Lime Shells	2500'	
2720	2750	Brk. Lime		
2750	2956	Lime	All G.K.	
2956	2970	Reebner Shale		
2970	2974	Leavenworth lime		
2974	2985	Snyderville Shale		
2985	3000	Dodge Lime		
3000	3015	Douglas Sand & Shale		
3015	3370	Lansing Lime		
3370	3443	Shale & Cong.		Bottom Plug at 105 ft. with 20 sacks cement -- Top Plug at 20 ft. with 15 sacks cement
3443	3480	Arbuckle Lime		
		Total Depth 3480'		
		Dry & Abandoned		

RECEIVED  
 C-3-8-49  
 MAR 8 - 1949  
 STATE COMMISSION  
 OIL & GAS  
 KANSAS

**PLUGGING**  
 FILE NO. 34-10-R-15D  
 BOOK PAGE 81 LINE 41